

UFC 4-141-10N  
16 January 2004

# UNIFIED FACILITIES CRITERIA (UFC)

---

## DESIGN: AVIATION OPERATION AND SUPPORT FACILITIES



APPROVED FOR PUBLIC RELEASE; DISTRIBUTION UNLIMITED

## UNIFIED FACILITIES CRITERIA (UFC)

**DESIGN: AVIATION OPERATION AND SUPPORT FACILITIES**

Any copyrighted material included in this UFC is identified at its point of use.  
Use of the copyrighted material apart from this UFC must have the permission of the  
copyright holder.

U.S. ARMY CORPS OF ENGINEERS (Preparing Activity)

NAVAL FACILITIES ENGINEERING COMMAND

AIR FORCE CIVIL ENGINEERING SUPPORT AGENCY

Record of Changes (changes indicated by \1\ ... /1/ )

<u>Change No.</u>	<u>Date</u>	<u>Location</u>

**UFC 4-141-10N**  
**16 January 2004**

## FOREWORD

The Unified Facilities Criteria (UFC) system is prescribed by MIL-STD 3007 and provides planning, design, construction, sustainment, restoration, and modernization criteria, and applies to the Military Departments, the Defense Agencies, and the DoD Field Activities in accordance with [USD\(AT&L\) Memorandum](#) dated 29 May 2002. UFC will be used for all DoD projects and work for other customers where appropriate. All construction outside of the United States is also governed by Status of forces Agreements (SOFA), Host Nation Funded Construction Agreements (HNFA), and in some instances, Bilateral Infrastructure Agreements (BIA.) Therefore, the acquisition team must ensure compliance with the more stringent of the UFC, the SOFA, the HNFA, and the BIA, as applicable.

UFC are living documents and will be periodically reviewed, updated, and made available to users as part of the Services' responsibility for providing technical criteria for military construction. Headquarters, U.S. Army Corps of Engineers (HQUSACE), Naval Facilities Engineering Command (NAVFAC), and Air Force Civil Engineer Support Agency (AFCESA) are responsible for administration of the UFC system. Defense agencies should contact the preparing service for document interpretation and improvements. Technical content of UFC is the responsibility of the cognizant DoD working group. Recommended changes with supporting rationale should be sent to the respective service proponent office by the following electronic form: [Criteria Change Request \(CCR\)](#). The form is also accessible from the Internet sites listed below.

UFC are effective upon issuance and are distributed only in electronic media from the following source:

- Whole Building Design Guide web site <http://dod.wbdg.org/>.

Hard copies of UFC printed from electronic media should be checked against the current electronic version prior to use to ensure that they are current.


AUTHORIZED BY:




DONALD L. BASHAM, P.E.  
 Chief, Engineering and Construction  
 U.S. Army Corps of Engineers



DR. JAMES W. WRIGHT, P.E.  
 Chief Engineer  
 Naval Facilities Engineering Command



KATHLEEN I. FERGUSON, P.E.  
 The Deputy Civil Engineer  
 DCS/Installations & Logistics  
 Department of the Air Force



Dr. GET W. MOY, P.E.  
 Director, Installations Requirements and  
 Management  
 Office of the Deputy Under Secretary of Defense  
 (Installations and Environment)

**CONTENTS**

	Page
CHAPTER 1 INTRODUCTION	
Paragraph 1-1 PURPOSE AND SCOPE .....	1-1
1-2 APPLICABILITY .....	1-1
1-2.1 General Building Requirements .....	1-1
1-2.2 Safety .....	1-1
1-2.3 Fire Protection .....	1-1
1-2.4 Antiterrorism/Force Protection .....	1-1
1-3 REFERENCES .....	1-1
APPENDIX A MIL-HDBK 1024/1.....	A-1

## CHAPTER 1

### INTRODUCTION

1-1 **PURPOSE AND SCOPE.** This UFC is comprised of two sections. Chapter 1 introduces this UFC and provides a listing of references to other Tri-Service documents closely related to the subject. Appendix A contains the full text copy of the previously released Military Handbook (MIL-HDBK) on this subject. This UFC serves as criteria until such time as the full text UFC is developed from the MIL-HDBK and other sources.

This UFC provides general criteria for the design of aviation operation and support facilities.

Note that this document does not constitute a detailed technical design, maintenance or operations manual, and is issued as a general guide to the considerations associated with design of economical, efficient, and environmentally acceptable aviation operation and support facilities.

1-2 **APPLICABILITY.** This UFC applies to all DoD Agencies and contractors preparing for designs of aviation operation and support facilities.

1-2.1 **GENERAL BUILDING REQUIREMENTS.** All DoD facilities must comply with UFC 1-200-01, *Design: General Building Requirements*. If any conflict occurs between this UFC and UFC 1-200-01, the requirements of UFC 1-200-01 take precedence.

1-2.2 **SAFETY.** All DoD facilities must comply with DODINST 6055.1 and applicable Occupational Safety and Health Administration (OSHA) safety and health standards.

**NOTE:** All **NAVY** projects, must comply with OPNAVINST 5100.23 (series), *Navy Occupational Safety and Health Program Manual*. The most recent publication in this series can be accessed at the NAVFAC Safety web site: [www.navfac.navy.mil/safety/pub.htm](http://www.navfac.navy.mil/safety/pub.htm). If any conflict occurs between this UFC and OPNAVINST 5100.23, the requirements of OPNAVINST 5100.23 take precedence.

1-2.3 **FIRE PROTECTION.** All DoD facilities must comply with UFC 3-600-01, *Design: Fire Protection Engineering for Facilities*. If any conflict occurs between this UFC and UFC 3-600-01, the requirements of UFC 3-600-01 take precedence.

1-2.4 **ANTITERRORISM/FORCE PROTECTION.** All DoD facilities must comply with UFC 4-010-01, *Design: DoD Minimum Antiterrorism Standards for Buildings*. If any conflict occurs between this UFC and UFC 4-010-01, the requirements of UFC 4-010-01 take precedence.

UFC 4-141-10N  
16 January 2004

**APPENDIX A**

**MIL-HDBK 1024/1  
AVIATION OPERATION AND SUPPORT FACILITIES**



+)))))))))  
\* INCH-POUND \*  
.)))))))))-  
MIL-HDBK-1024/1  
15 FEBRUARY 1994

MILITARY HANDBOOK

AVIATION OPERATIONAL AND SUPPORT FACILITIES

AMSC N/A

AREA FACR

DISTRIBUTION STATEMENT A. APPROVED FOR PUBLIC RELEASE. DISTRIBUTION IS UNLIMITED.

MIL-HDBK-1024/1

ABSTRACT

Basic guidance for the planning, engineering, and design of Navy aviation operational and support facilities is presented for use by facility planners, engineers, and architects. Subject guidance addresses building layouts, utility requirements, and functional relationships between spaces.

MIL-HDBK-1024/1

FOREWORD

This handbook was developed to provide guidance on the planning, engineering, and design for Naval aviation operational and support facilities, and uses, to the maximum extent possible, national and institute standards in accordance with Naval Facilities Engineering Command (NAVFACENGCOM) policy. Source data and material used in the preparation of this handbook include current Department of Defense (DOD) and Department of Transportation directives, technical manuals, field studies, observations, and reports of research and development which promote standardization and provide optimum support facilities.

Recommendations for improvement are encouraged from within the Navy, other Government agencies, and the private sector and should be furnished on the DD Form 1426 provided inside the back cover and forwarded to: Commanding Officer, Southern Division, Naval Facilities Engineering Command, Code 4041, P.O. Box 190010, North Charleston, SC 29419-9010; Telephone (803) 743-0423.

THIS HANDBOOK SHALL NOT BE USED AS A REFERENCE DOCUMENT FOR PROCUREMENT OF FACILITIES CONSTRUCTION. IT IS TO BE USED IN THE PURCHASE OF FACILITIES ENGINEERING STUDIES AND DESIGN (FINAL PLANS, SPECIFICATIONS, AND COST ESTIMATES). DO NOT REFERENCE IT IN MILITARY OR FEDERAL SPECIFICATIONS OR OTHER PROCUREMENT DOCUMENTS.

MIL-HDBK-1024/1

SUPPORT FACILITIES CRITERIA MANUALS

<u>Criteria Manual</u>	<u>Title</u>	<u>PA</u>
MIL-HDBK-1024/1	Aviation Operational and Support Facilities	SOUTHDIV
MIL-HDBK-1024/3	Oxyacetylene and Nitrogen and Breathing Oxygen Facilities	WESTDIV
MIL-HDBK-1024/4	Ships Support Facilities (Proposed)	PACDIV
MIL-HDBK-1024/5	Logistics Support Facilities (Proposed)	CHESDIV

## MIL-HDBK-1024/1

## AVIATION OPERATIONAL AND SUPPORT FACILITIES

## CONTENTS

		<u>Page</u>
<b>Section 1</b>	<b>INTRODUCTION</b>	
1.1	Scope . . . . .	1
1.2	Purpose of Criteria . . . . .	1
1.3	Predesign Programming . . . . .	1
1.3.1	Chief of Naval Operations (CNO) . . . . .	1
1.3.2	Naval Facilities Engineering Command (NAVFACENCOM) . . . . .	2
1.3.3	Naval Air Systems Command (NAVAIRSYSCOM)	2
1.3.4	Space and Naval Warfare Systems Command (SPAWARSYSCOM) . . . . .	3
1.3.5	Maintenance Authority . . . . .	3
1.3.6	Designer . . . . .	3
1.3.6.1	Base Electronic Systems Engineering Plan (BESEP) . . . . .	3
1.3.6.2	Intrusion Detection Systems Engineering Plan (IDSEP) . . . . .	4
1.4	Policy Statement . . . . .	4
<b>Section 2</b>	<b>GENERAL DESIGN CRITERIA</b>	
2.1	Facility Planning . . . . .	5
2.2	Site Considerations . . . . .	5
2.2.1	Site Suitability . . . . .	5
2.2.2	Separation of Structures . . . . .	5
2.2.3	Access and Parking . . . . .	5
2.2.3.1	Parking . . . . .	5
2.2.3.2	Access for Fire Department Apparatus . .	6
2.2.4	Site Drainage . . . . .	6
2.2.5	Protection of Fixed Objects . . . . .	6
2.2.6	Airfield Safety . . . . .	6
2.2.6.1	Objects Located on Airfield . . . . .	6
2.2.6.2	Objects in Violation of Airfield Safety Criteria . . . . .	6
2.3	Architectural and Structural Requirements	7
2.3.1	Acoustics . . . . .	7
2.3.2	Handicapped Employees . . . . .	7
2.3.3	Structural Design . . . . .	8

## MIL-HDBK-1024/1

		<u>Page</u>
2.3.3.1	Lateral Loads . . . . .	8
2.3.3.2	Antenna Supports . . . . .	8
2.3.4	Construction Materials . . . . .	8
2.3.4.1	Reflective Surfaces . . . . .	8
2.3.5	Floors . . . . .	8
2.3.5.1	Permanent Floors . . . . .	11
2.3.5.2	Access Flooring . . . . .	11
2.3.6	Roofing . . . . .	11
2.3.7	Walls . . . . .	11
2.3.7.1	Thermal Insulation and Vapor Retarders . . . . .	11
2.3.7.2	Exterior Walls . . . . .	11
2.3.7.3	Interior Walls . . . . .	12
2.3.8	Interior Finishes . . . . .	12
2.3.8.1	Sealed Concrete Floors . . . . .	12
2.3.8.2	Resilient Flooring . . . . .	12
2.3.8.3	Ceramic Tile Flooring . . . . .	12
2.3.8.4	Carpet Flooring . . . . .	12
2.3.8.5	Masonry Finish Walls . . . . .	12
2.3.8.6	Painted Finish Walls . . . . .	12
2.3.8.7	Ceramic Tile Finish Walls . . . . .	12
2.3.8.8	Exposed Structure Ceilings . . . . .	12
2.3.8.9	Acoustical Tile Ceilings . . . . .	12
2.3.8.10	Shower Ceilings . . . . .	12
2.3.9	Doors . . . . .	13
2.3.9.1	Exterior Doors . . . . .	13
2.3.9.2	Interior Doors . . . . .	13
2.3.9.3	Overhead Doors . . . . .	13
2.3.9.4	Door Hardware . . . . .	13
2.3.9.5	Hinges . . . . .	13
2.3.9.6	Locksets . . . . .	13
2.3.9.7	Exit Devices (Panic Hardware) . . . . .	13
2.3.9.8	Closers . . . . .	14
2.3.10	Windows . . . . .	14
2.3.10.1	Service Windows . . . . .	14
2.3.11	Ladders . . . . .	14
2.3.12	Pre-engineered, Premanufactured Buildings . . . . .	14
2.4	Mechanical Engineering . . . . .	14
2.4.1	Energy Conservation . . . . .	14
2.4.2	Equipment Selection . . . . .	14
2.4.3	Heating and Air Conditioning . . . . .	14
2.4.4	Ventilation . . . . .	16
2.4.4.1	Battery Shops . . . . .	16
2.4.5	Outside Weather Conditions . . . . .	16
2.4.6	Inside Design Conditions . . . . .	17
2.4.6.1	Personnel Comfort . . . . .	17
2.4.6.2	Computer and Electronic Rooms . . . . .	17

## MIL-HDBK-1024/1

	<u>Page</u>	
2.4.6.3	Storage Areas . . . . .	17
2.4.7	Plumbing . . . . .	17
2.4.7.1	Battery Shops . . . . .	17
2.4.8	Water and Sanitation . . . . .	17
2.4.9	Fire Protection . . . . .	18
2.4.9.1	Electronic Equipment Areas . . . . .	18
2.4.9.2	Emergency Generator Protection . . . . .	18
2.4.9.3	Portable Fire Extinguishers . . . . .	18
2.4.9.4	Underfloor Spaces . . . . .	18
2.4.9.5	Automatic Sprinkler Systems . . . . .	18
2.4.9.6	Standpipe Systems . . . . .	18
2.4.9.7	Halon Fire Protection Systems . . . . .	18
2.4.9.8	Hydrants . . . . .	18
2.4.9.9	Elevators . . . . .	18
2.4.10	Noise and Vibration Control . . . . .	19
2.5	Electrical Engineering . . . . .	19
2.5.1	General Requirements . . . . .	19
2.5.2	Distribution Panels . . . . .	19
2.5.3	Incoming Power . . . . .	20
2.5.4	Separate Buses . . . . .	20
2.5.5	Lightning Protection . . . . .	20
2.5.6	Lighting . . . . .	20
2.5.6.1	Interior Lighting . . . . .	20
2.5.6.2	Exterior Lighting . . . . .	20
2.5.7	Emergency Electrical Power . . . . .	20
2.5.7.1	Emergency Generator . . . . .	20
2.5.7.2	Emergency Generator Fuel Storage . . . . .	22
2.5.8	Uninterrupted Power Supply (UPS) . . . . .	22
2.5.9	400-Hertz (Hz) Power . . . . .	22
2.5.10	Fire Alarm and Detection Systems . . . . .	24
2.5.10.1	Signal Transmission . . . . .	24
2.5.10.2	Electronic Equipment Spaces . . . . .	24
2.5.10.3	Raised Floor Cable Spaces . . . . .	24
2.5.10.4	Remote and Unattended Facilities . . . . .	24
2.5.10.5	Occupied Buildings . . . . .	24
2.5.11	Communications Systems . . . . .	24
2.6	Physical Security . . . . .	24
2.6.1	General Requirements . . . . .	24
2.6.2	Exterior Physical Security . . . . .	25
2.6.2.1	Perimeter Fencing . . . . .	25
2.6.2.2	Security Lighting . . . . .	26
2.6.2.3	Intrusion Detection Systems (IDS) . . . . .	26
2.6.2.4	Closed Circuit Television (CCTV) . . . . .	26
2.6.3	Interior Physical Security . . . . .	27

## MIL-HDBK-1024/1

		<u>Page</u>
2.6.3.1	Delay Times . . . . .	27
2.6.3.2	Building Layout . . . . .	27
2.6.3.3	Wall Construction . . . . .	27
2.6.3.4	Roof and Floor Construction . . . . .	27
2.6.3.5	Exterior Doors . . . . .	27
2.6.3.6	Windows, Air Vents, and Ducts . . . . .	27
2.6.3.7	Roof Doors and Hatches . . . . .	27
2.6.3.8	Cipher Locks . . . . .	27
2.6.4	Vaults . . . . .	28
2.6.4.1	Safety and Emergency Devices . . . . .	28
2.6.4.2	Fire Protection . . . . .	28
2.7	Safety and Health . . . . .	28
2.7.1	General Requirements . . . . .	28
2.7.2	Human Engineering . . . . .	28
2.7.3	Electromagnetic Hazards . . . . .	28
2.7.4	Fire Protection . . . . .	29
2.7.4.1	Classifications . . . . .	29
2.7.4.2	Windowless Buildings . . . . .	29
2.7.5	Life Safety . . . . .	29
2.8	Design Standards . . . . .	29
<b>Section 3</b>	<b>AIR NAVIGATION AIDS/AIRCRAFT LANDING SYSTEMS</b>	
3.1	Air Navigation Aids . . . . .	30
3.1.1	Function . . . . .	30
3.1.1.1	Very High Frequency (VHF)	
	Omni-Directional Range (VOR) . . . . .	30
3.1.1.2	Tactical Air Navigation (TACAN) . . . . .	30
3.1.1.3	Very High Frequency (VHF) Omni-Directional Range/Tactical Air Navigation (VORTAC) . . . . .	30
3.1.2	Location . . . . .	30
3.1.3	Architectural and Structural Requirements	30
3.1.3.1	Structure . . . . .	30
3.1.3.2	Windows . . . . .	43
3.1.3.3	Premanufactured Building . . . . .	43
3.1.4	Electrical Requirements . . . . .	43
3.1.4.1	Emergency Electrical Power . . . . .	43
3.1.5	Security . . . . .	43
3.1.6	Additional Design Criteria . . . . .	43
3.2	Aircraft Landing Systems . . . . .	43
3.2.1	Microwave Landing System (MLS)/ Instrument Landing System (ILS) . . . . .	43
3.2.1.1	Function . . . . .	43
3.2.1.2	Microwave Landing System . . . . .	43

## MIL-HDBK-1024/1

	<u>Page</u>	
3.2.1.3	Instrument Landing System . . . . .	43
3.2.1.4	Location - MLS Transmitters . . . . .	43
3.2.1.5	Location - ILS Transmitters . . . . .	54
3.2.1.6	Structure . . . . .	54
3.2.1.7	Mechanical . . . . .	54
3.2.1.8	Electrical . . . . .	54
3.2.1.9	Emergency Electrical Power . . . . .	54
3.2.1.10	Lighting . . . . .	54
3.2.1.11	Site Work . . . . .	54
3.2.1.12	Security . . . . .	54
3.2.1.13	Additional Design Criteria . . . . .	54
3.2.2	Precision Approach Landing System (PALS)/ Precision Approach Radar (PAR) . . . . .	54
3.2.2.1	Function . . . . .	54
3.2.2.2	Precision Approach Landing System (PALS)	55
3.2.2.3	Precision Approach Radar (PAR) . . . . .	55
3.2.2.4	Location . . . . .	55
3.2.2.5	Structure . . . . .	55
3.2.2.6	Mechanical Requirements . . . . .	55
3.2.2.7	Electrical Requirements . . . . .	55
3.2.2.8	Emergency Electrical Power . . . . .	55
3.2.2.9	Lighting . . . . .	55
3.2.2.10	Paved Equipment Areas . . . . .	55
3.2.2.11	Security . . . . .	68
3.2.2.12	Additional Design Criteria . . . . .	68
Section 4	<b>AIR SURVEILLANCE RADAR SYSTEMS</b>	
4.1	Function . . . . .	69
4.2	Radar Systems . . . . .	69
4.2.1	Airport Surveillance Radar (ASR) . . . . .	69
4.2.2	Air Route Surveillance Radar (ARSR) . . . . .	69
4.3	Location . . . . .	69
4.4	Architectural and Structural Requirements	69
4.4.1	Structure . . . . .	69
4.4.2	Floors . . . . .	69
4.4.3	Ceilings . . . . .	76
4.4.4	Windows . . . . .	76
4.5	Mechanical Requirements . . . . .	76
4.5.1	Heating . . . . .	76
4.5.2	Air Conditioning . . . . .	76
4.6	Electrical Requirements . . . . .	76
4.6.1	Emergency Electrical Power . . . . .	76
4.6.2	Uninterrupted Power Supply (UPS) . . . . .	76
4.7	Security . . . . .	76
4.8	Additional Design Criteria . . . . .	76

## MIL-HDBK-1024/1

		<u>Page</u>
Section	5	COMMUNICATIONS FACILITIES
5.1	Function . . . . .	77
5.1.1	Radio Receiver Building . . . . .	77
5.1.2	Radio Transmitter Building . . . . .	77
5.1.3	Collocated Radio Transmitter and Receiver Building . . . . .	77
5.1.4	Remote Data Link Building . . . . .	77
5.2	Location . . . . .	77
5.3	Architectural and Structural Requirements	77
5.3.1	Structure . . . . .	77
5.3.2	Windows . . . . .	77
5.3.3	Premanufactured Buildings . . . . .	90
5.4	Electrical Requirements . . . . .	90
5.4.1	Emergency Electrical Power . . . . .	90
5.5	Security . . . . .	90
5.6	Additional Design Criteria . . . . .	90
Section	6	AIR TRAFFIC CONTROL FACILITIES
6.1	Military Terminal Radar Approach Control Facility (MTRACON) . . . . .	91
6.1.1	Function . . . . .	91
6.1.2	Location . . . . .	91
6.1.3	Architectural and Structural Requirements	91
6.1.3.1	Windows . . . . .	91
6.1.4	Electrical Requirements . . . . .	91
6.1.4.1	Uninterrupted Power Supply (UPS) . . . . .	95
6.1.4.2	Emergency Electrical Power . . . . .	95
6.1.4.3	400-Hz Power . . . . .	95
6.1.5	Lighting . . . . .	95
6.1.6	Security . . . . .	95
6.1.7	Additional Design Criteria . . . . .	95
6.2	Fleet Area Control and Surveillance Facility (FACSFAC) . . . . .	95
6.2.1	Function . . . . .	95
6.2.2	Location . . . . .	96
6.2.3	Architectural and Structural Requirements	96
6.2.3.1	Windows . . . . .	96
6.2.4	Mechanical Requirements . . . . .	96
6.2.4.1	Air Conditioning . . . . .	100
6.2.4.2	Heating . . . . .	100
6.2.5	Electrical Requirements . . . . .	100
6.2.5.1	Uninterrupted Power Supply (UPS) . . . . .	100
6.2.5.2	Emergency Electrical Power . . . . .	100
6.2.5.3	400-Hz Power . . . . .	101

## MIL-HDBK-1024/1

	<u>Page</u>
6.2.6	Security . . . . . 101
6.2.7	Additional Design Criteria . . . . . 101
6.3	Joint Control Facility (JCF) . . . . . 101
6.3.1	Function . . . . . 101
6.3.2	Location . . . . . 101
6.3.3	Architectural and Structural Requirements 102
6.3.3.1	Windows . . . . . 102
6.3.4	Mechanical Requirements . . . . . 102
6.3.4.1	Air Conditioning . . . . . 110
6.3.4.2	Heating . . . . . 110
6.3.5	Electrical Requirements . . . . . 110
6.3.5.1	Uninterrupted Power Supply (UPS) . . . . . 110
6.3.5.2	Emergency Electrical Power . . . . . 110
6.3.5.3	400-Hz Power . . . . . 111
6.3.6	Lighting . . . . . 111
6.3.7	Security . . . . . 111
6.3.8	Additional Design Criteria . . . . . 111
6.4	Air Traffic Control Tower . . . . . 111
6.4.1	Function . . . . . 111
6.4.2	Tower Location and Height . . . . . 111
6.4.3	Architectural and Structural Requirements 112
6.4.3.1	Interior Walls . . . . . 112
6.4.3.2	Windows . . . . . 119
6.4.4	Mechanical Requirements . . . . . 119
6.4.5	Electrical Requirements . . . . . 119
6.4.5.1	Emergency Electrical Power . . . . . 119
6.4.5.2	Uninterrupted Power Supply (UPS) . . . . . 119
6.4.6	Lighting . . . . . 119
6.4.7	Fire Protection . . . . . 119
6.4.8	Security . . . . . 119
6.4.9	Additional Design Criteria . . . . . 120
6.5	Air Traffic Control Tower Base Building . 120
6.5.1	Function . . . . . 120
6.5.2	Location . . . . . 120
6.5.3	Architectural and Structural Requirements 120
6.5.3.1	Windows . . . . . 120
6.5.4	Electrical Requirements . . . . . 120
6.5.4.1	Uninterrupted Power Supply (UPS) . . . . . 120
6.5.4.2	Emergency Electrical Power . . . . . 124
6.5.4.3	400-Hz Power . . . . . 124
6.5.5	Lighting . . . . . 124
6.5.6	Security . . . . . 124
6.5.7	Additional Design Criteria . . . . . 124

## MIL-HDBK-1024/1

		<u>Page</u>
Section	7	METEOROLOGICAL FACILITIES
7.1	Function . . . . .	125
7.1.1	Fleet Weather Central . . . . .	125
7.1.2	Fleet Weather Facility . . . . .	125
7.2	Location . . . . .	125
7.3	Architectural and Structural Requirements	125
7.3.1	Overhead Doors . . . . .	125
7.4	Electrical Requirements . . . . .	132
7.4.1	Emergency Electrical Power . . . . .	132
7.4.2	Uninterrupted Power Supply (UPS) . . . . .	132
7.5	Security . . . . .	132
7.6	Additional Design Criteria . . . . .	132
Section	8	SPECIAL SUPPORT FACILITIES
8.1	Air Operations Building . . . . .	133
8.1.1	Function . . . . .	133
8.1.2	Location . . . . .	133
8.1.3	Architectural and Structural Requirements	133
8.1.3.1	Windows . . . . .	133
8.1.4	Electrical Requirements . . . . .	133
8.1.4.1	Emergency Electrical Power . . . . .	133
8.1.5	Security . . . . .	138
8.1.6	Additional Design Criteria . . . . .	138
8.2	Fleet Reconnaissance Photographic Laboratory . . . . .	138
8.2.1	Function . . . . .	138
8.2.2	Location . . . . .	138
8.2.3	Architectural and Structural Requirements	138
8.2.3.1	Floors . . . . .	138
8.2.3.2	Light-Trap Doors . . . . .	142
8.2.4	Mechanical Requirements . . . . .	142
8.2.4.1	Heating and Air Conditioning . . . . .	142
8.2.4.2	Ventilation . . . . .	142
8.2.4.3	Plumbing . . . . .	142
8.2.5	Electrical Requirements . . . . .	142
8.2.5.1	Emergency Electrical Power . . . . .	142
8.2.6	Security . . . . .	143
8.2.7	Hazardous Waste Storage . . . . .	143
8.2.8	Additional Design Criteria . . . . .	143
8.3	Anti-Submarine Warfare Operations Center (ASWOC) . . . . .	143
8.3.1	Function . . . . .	143
8.3.2	Location . . . . .	143

## MIL-HDBK-1024/1

	<u>Page</u>	
8.3.3	Architectural and Structural Requirements	143
8.3.3.1	Windows . . . . .	151
8.3.4	Mechanical Requirements . . . . .	151
8.3.4.1	Ventilation . . . . .	151
8.3.5	Electrical Requirements . . . . .	151
8.3.5.1	Uninterrupted Power Supply (UPS) . . . . .	151
8.3.5.2	Emergency Electrical Power . . . . .	152
8.3.6	Security . . . . .	152
8.3.7	Additional Design Criteria . . . . .	152
8.4	Air Cargo Terminal . . . . .	152
8.4.1	Function . . . . .	152
8.4.2	Location . . . . .	152
8.4.3	Architectural and Structural Requirements	153
8.4.3.1	Structure . . . . .	153
8.4.3.2	Wire Mesh Partitions . . . . .	153
8.4.3.3	Interior Doors . . . . .	153
8.4.3.4	Overhead Doors . . . . .	153
8.4.3.5	Pre-engineered Buildings . . . . .	153
8.4.4	Mechanical Requirements . . . . .	153
8.4.4.1	Heating . . . . .	159
8.4.4.2	Ventilation . . . . .	159
8.4.4.3	Sawdust Collection and Control . . . . .	159
8.4.4.4	Fire Protection . . . . .	159
8.4.5	Electrical Requirements . . . . .	159
8.4.5.1	Emergency Electrical Power . . . . .	159
8.4.6	Lighting . . . . .	159
8.4.7	Security . . . . .	159
8.4.8	Additional Design Criteria . . . . .	159
8.5	Air Passenger Terminal . . . . .	159
8.5.1	Function . . . . .	159
8.5.2	Location . . . . .	160
8.5.3	Architectural and Structural Requirements	160
8.5.3.1	Wire Mesh Partitions . . . . .	160
8.5.3.2	Ceilings . . . . .	160
8.5.3.3	Overhead Doors . . . . .	160
8.5.3.4	Windows . . . . .	160
8.5.3.5	Pre-engineered Buildings . . . . .	160
8.5.4	Electrical Requirements . . . . .	164
8.5.4.1	Emergency Electrical Power . . . . .	164
8.5.5	Security . . . . .	164
8.5.6	Additional Design Criteria . . . . .	164
8.6	Aircraft Fire and Rescue Station and Combined Structural/Aircraft Fire and Rescue Station . . . . .	164

## MIL-HDBK-1024/1

			<u>Page</u>
8.6.1	Function . . . . .		164
8.6.2	Location . . . . .		164
8.6.3	Architectural and Structural Requirements		164
8.6.3.1	Interior Walls . . . . .		172
8.6.3.2	Floors . . . . .		172
8.6.3.3	Interior Doors . . . . .		172
8.6.3.4	Overhead Doors . . . . .		172
8.6.4	Mechanical Requirements . . . . .		172
8.6.4.1	Heating . . . . .		172
8.6.4.2	Ventilation . . . . .		173
8.6.4.3	Plumbing . . . . .		173
8.6.5	Electrical Requirements . . . . .		173
8.6.5.1	Emergency Electrical Power . . . . .		173
8.6.6	Pavement . . . . .		173
8.6.7	Drainage . . . . .		173
8.6.8	Security . . . . .		174
8.6.9	Additional Design Criteria . . . . .		174
 FACILITY PLATES  			
133-25	1 of 4	VOR Facility Site Plan . . . . .	31
133-25	2 of 4	VOR Building Layout . . . . .	32
133-25	3 of 4	VOR Building Section . . . . .	33
133-25	4 of 4	VOR Facility Design Notes . . . . .	34
133-25	1 of 4	TACAN Facility Site Plan . . . . .	35
133-25	2 of 4	TACAN Building Layout . . . . .	36
133-25	3 of 4	TACAN Building Section . . . . .	37
133-25	4 of 4	TACAN Facility Design Notes . . . . .	38
133-25	1 of 4	VORTAC Facility Site Plan . . . . .	39
133-25	2 of 4	VORTAC Building Layout . . . . .	40
133-25	3 of 4	VORTAC Building Section . . . . .	41
133-25	4 of 4	VORTAC Facility Design Notes . . . . .	42
134-40	1 of 4	MLS Facility: Site Plan . . . . .	44
134-40	2 of 4	MLS Facility: Azimuth Station Site Plan	45
134-40	3 of 4	MLS Facility: Elevation Station Site Plan . . . . .	46
134-40	4 of 4	MLS Facility Design Notes . . . . .	47
134-40	1 of 6	ILS Facility: Marker Siting . . . . .	48
134-40	2 of 6	ILS Facility: Outer and Middle Markers .	49
134-40	3 of 6	ILS Facility: Runway Site Plan . . . . .	50
134-40	4 of 6	ILS Facility: Localizer Equipment and Antenna Site Plan . . . . .	51
134-40	5 of 6	ILS Facility: Glide Slope Equipment and Antenna Site Plan . . . . .	52
134-40	6 of 6	ILS Facility Design Notes . . . . .	53
134-40	1 of 4	PALS Facility Siting Criteria . . . . .	56

MIL-HDBK-1024/1

			<u>Page</u>
134-40	2 of 4	PALS Facility Site Plan . . . . .	57
134-40	3 of 4	PALS Facility Electrical Hardstand . . . . .	58
134-40	4 of 4	PALS Facility Design Notes . . . . .	59
134-40	1 of 8	PAR Facility Siting Criteria . . . . .	60
134-40	2 of 8	PAR Facility Site Plan . . . . .	61
134-40	3 of 8	PAR Facility: Turntable Mounted Radar Plan . . . . .	62
134-40	4 of 8	PAR Facility: Turntable Mounted Radar Elevation . . . . .	63
134-40	5 of 8	PAR Facility: Fixed Mounted Radar Plan . . . . .	64
134-40	6 of 8	PAR Facility: Fixed Mounted Radar Elevation . . . . .	65
134-40	7 of 8	PAR Facility Electrical Hardstand . . . . .	66
134-40	8 of 8	PAR Facility Design Notes . . . . .	67
133-75	1 of 3	ASR Facility Site Plan . . . . .	70
133-75	2 of 3	ASR Building Layout . . . . .	71
133-75	3 of 3	ASR Facility Design Notes . . . . .	72
133-76	1 of 3	ARSR Facility Site Plan . . . . .	73
133-76	2 of 3	ARSR Building Layout . . . . .	74
133-76	3 of 3	ARSR Facility Design Notes . . . . .	75
131-35	1 of 3	Radio Receiver Facility Site Plan . . . . .	78
131-35	2 of 3	Radio Receiver Building Layout . . . . .	79
131-35	3 of 3	Radio Receiver Facility Design Notes . . . . .	80
131-50	1 of 3	Radio Transmitter Facility Site Plan . . . . .	81
131-50	2 of 3	Radio Transmitter Building Layout . . . . .	82
131-50	3 of 3	Radio Transmitter Facility Design Notes . . . . .	83
131-35/50	1 of 3	Collocated Radio Transmitter and Receiver Facility Site Plan . . . . .	84
131-35/50	2 of 3	Collocated Radio Transmitter and Receiver Building Layout . . . . .	85
131-35/50	3 of 3	Collocated Radio Transmitter and Receiver Facility Design Notes . . . . .	86
131-20	1 of 3	Remote Data Link Facility Site Plan . . . . .	87
131-20	2 of 3	Remote Data Link Building Layout . . . . .	88
131-20	3 of 3	Remote Data Link Facility Design Notes . . . . .	89
133-72	1 of 3	MTRACON Facility Site Plan . . . . .	92
133-72	2 of 3	MTRACON Building Layout . . . . .	93
133-72	3 of 3	MTRACON Facility Design Notes . . . . .	94
133-73	1 of 3	FACSFAC Facility Site Plan . . . . .	97
133-73	2 of 3	FACSFAC Building Layout . . . . .	98
133-73	3 of 3	FACSFAC Facility Design Notes . . . . .	99
133-74	1 of 7	Joint Control Facility (Medium Density) Site Plan . . . . .	103
133-74	2 of 7	Joint Control Facility (High Density) Site Plan . . . . .	104
133-74	3 of 7	Joint Control Facility (Medium Density) Building Layout . . . . .	105

MIL-HDBK-1024/1

			<u>Page</u>
133-74	4 of 7	Joint Control Facility (High Density) Building Layout . . . . .	106
133-74	5 of 7	Joint Control Facility (High Density) Building Layout - Part 1 . . . . .	107
133-74	6 of 7	Joint Control Facility (High Density) Building Layout - Part 2 . . . . .	108
133-74	7 of 7	Joint Control Facility Design Notes . . . . .	109
141-70	1 of 6	Air Traffic Control Tower Section . . . . .	113
141-70	2 of 6	Air Traffic Control Tower Typical Floor Layout . . . . .	114
141-70	3 of 6	Air Traffic Control Tower (Low Density) Tower Cab Layout . . . . .	115
141-70	4 of 6	Air Traffic Control Tower (High Density) Tower Cab Layout . . . . .	116
141-70	5 of 6	Air Traffic Control Tower Cab Roof Plan . . . . .	117
141-70	6 of 6	Air Traffic Control Tower Facility Design Notes . . . . .	118
141-71	1 of 3	Air Traffic Control Tower Base Building Facility Site Plan . . . . .	121
141-71	2 of 3	Air Traffic Control Tower Base Building Layout . . . . .	122
141-71	3 of 3	Air Traffic Control Tower Base Building Facility Design Notes . . . . .	123
137-10	1 of 6	Fleet Weather Central Facility Site Plan . . . . .	126
137-10	2 of 6	Fleet Weather Central Facility Building Layout . . . . .	127
137-10	3 of 6	Fleet Weather Central Facility Design Notes . . . . .	128
137-10	4 of 6	Fleet Weather Facility Site Plan . . . . .	129
137-10	5 of 6	Fleet Weather Facility Building Layout . . . . .	130
137-10	6 of 6	Fleet Weather Facility Design Notes . . . . .	131
141-40	1 of 4	Air Operations Building Facility Site Plan . . . . .	134
141-40	2 of 4	Air Operations Building First Floor Layout . . . . .	135
141-40	3 of 4	Air Operations Building Second Floor Layout . . . . .	136
141-40	4 of 4	Air Operations Building Facility Design Notes . . . . .	137
141-65	1 of 3	Fleet Reconnaissance Photographic Laboratory Facility Site Plan . . . . .	139
141-65	2 of 3	Fleet Reconnaissance Photographic Laboratory Building Layout . . . . .	140
141-65	3 of 3	Fleet Reconnaissance Photographic Laboratory Facility Design Notes . . . . .	141
141-42	1 of 7	ASWOC Single-Story Facility Site Plan . . . . .	144
141-42	2 of 7	ASWOC Two-Story Facility Site Plan . . . . .	145

## MIL-HDBK-1024/1

			<u>Page</u>
141-42	3 of 7	ASWOC Single-Story Building Layout Part A . . . . .	146
141-42	4 of 7	ASWOC Single-Story Building Layout Part B . . . . .	147
141-42	5 of 7	ASWOC Two-Story Building Layout Lower Level . . . . .	148
141-42	6 of 7	ASWOC Two-Story Building Layout Upper Level . . . . .	149
141-42	7 of 7	ASWOC Facility Design Notes . . . . .	150
141-12	1 of 5	Air Cargo Terminal (Small) Facility Site Plan . . . . .	154
141-12	2 of 5	Air Cargo Terminal (Medium/Large) Facility Site Plan . . . . .	155
141-12	3 of 5	Air Cargo Terminal (Small) Building Layout . . . . .	156
141-12	4 of 5	Air Cargo Terminal Building (Medium/Large) Building Layout . . . . .	157
141-12	5 of 5	Air Cargo Terminal Facility Design Notes	158
141-11	1 of 3	Air Passenger Terminal Facility Site Plan	161
141-11	2 of 3	Air Passenger Terminal Building Layout .	162
141-11	3 of 3	Air Passenger Terminal Facility Design Notes . . . . .	163
141-20	1 of 4	Aircraft Fire and Rescue Station (Class A & B) Site Plan . . . . .	165
141-20	2 of 4	Aircraft Fire and Rescue Station Building Layout Class A . . . . .	166
141-20	3 of 4	Aircraft Fire and Rescue Station Building Layout Class B . . . . .	167
141-20	4 of 4	Aircraft Fire and Rescue Station (Class A & B) Facility Design Notes . .	168
141-25	1 of 3	Combined Structural/Aircraft Fire and Rescue Station Site Plan . . . . .	169
141-25	2 of 3	Combined Structural/Aircraft Fire and Rescue Station Building Layout . . . . .	170
141-25	3 of 3	Combined Structural/ Aircraft Fire and Rescue Station Facility Design Notes .	171

## FIGURES

Figure	1	Radio Antenna Tower . . . . .	9
	2	ASR Antenna Tower . . . . .	10
	3	Prefabricated Building . . . . .	15
	4	Indoor Emergency Generator Room Layout .	21
	5	Prefabricated Indoor Emergency Generator Room Layout . . . . .	23

MIL-HDBK-1024/1

	<u>Page</u>
REFERENCES . . . . .	175
GLOSSARY . . . . .	183

## MIL-HDBK-1024/1

## Section 1: INTRODUCTION

1.1 Scope. This military handbook, MIL-HDBK-1024/1, contains guidance for (Navy and Contract) planners, engineers, and architects on the planning, engineering, and design of Department of the Navy aviation operational and support facilities. This is supplementary guidance to be used in conjunction with Base Electronic Systems Engineering Plans (BESEPs), Intrusion Detection Systems Engineering Plans (IDSEPs), Base Exterior Architecture Plans (BEAPs), and other DOD and Department of Transportation material for the planning and construction of Naval aviation operational and support facilities and the preparation of DD 1391 Military Construction and Step II Special Project Submissions. It is assumed that general architectural and engineering standards are known or available to the planner. Navy criteria concerning basic and detailed construction and engineering criteria are not addressed in this handbook and are a prerequisite for facility planning.

1.2 Purpose of Criteria. Subject guidance will be used for planning individual projects, preparing engineering documentation, and preparing contractual documents for construction. It is intended to present the basis for standardization of practices and identify a common baseline to be used as a guide during the planning of new facilities or the modification of existing facilities.

1.3 Predesign Programming. Naval aviation is a highly dynamic field which depends on state-of-the-art computer technology and the design of Navy aviation operational and support facilities requires close coordination between the designer and other parties. Consider a predesign programming session at the host activity to establish specific requirements for the proposed facility. Responsibilities involved in predesign stages are as follows:

1.3.1 Chief of Naval Operations (CNO). The CNO is the Director of Naval Communications, who sponsors and supports Naval communications facilities through the Naval Telecommunications Command and other commands. The CNO, as the user, states the needs of the operating and supporting facilities for research and development, improved equipment, new equipment, spare and repair parts, consumables, training, maintenance, personnel facilities, and any other requirements of the user. In many instances, the CNO is responsible for supporting the Defense Informations Systems Agency (DISA), which is the sponsor for the nation's world-wide Defense Communications System (DCS). CNO, Code OP-N885F2, is the governing body or Operations Navy (OPNAV) sponsor for Naval Air Traffic Control (ATC), Air Navigation Aids and Landing Systems (NAALS) programs, operations, and funding. CNO is responsible for formulating policies, directives, procedures and guidelines which govern planning, programming and implementation of the NAALS ATC program and associated equipment for use at naval aviation shore facilities. CNO is responsible for validating Operational Requirements, approving Operational Capability Improvement Requests (OCIRs), representing the Navy in interagency agreements with the Federal Aviation Administration (FAA) and other Department of Defense

MIL-HDBK-1024/1

(DOD) components and appropriating funds for NAALS acquisition, research, development, testing, evaluation, operations, and maintenance.

1.3.2 Naval Facilities Engineering Command (NAVFACENGCOM). NAVFACENGCOM is responsible for design, development, and construction of the facilities ancillary to and/or required for support or housing of electronic equipment and operating personnel. NAVFACENGCOM provides technical guidance and direction in shore facility engineering from project inception to completion. In support of ATC electronic facilities construction, NAVFACENGCOM works closely with Naval-in-Service Engineering, East Coast Division (NISE-EAST), Charleston, SC. NISE-EAST is responsible for preparing preliminary and final Military Construction (MILCON) BESEPs and assisting the user with submitting site approval requests using Request for Projects Site Approval (NAVFAC Form 11010/31) to ensure that facilities projects are sited per the activity master plan to ensure compliance with applicable safety and environmental criteria. During the design phase, NISE-EAST is responsible for assisting NAVFACENGCOM with preparing project engineering documentation: required facilities information, TEMPEST and security requirements, and technical data necessary for initial project planning and design and providing NAVFAC with a brief overall description and design concepts of proposed projects to permit evaluation of the proposed installation. In addition, NISE-EAST is responsible for reviewing DD 1391, supporting NAVFACENGCOM and the architectural-engineer (A-E) during the project design phases and attending predesign, 35 percent, 100 percent, and other required design review conferences.

1.3.3 Naval Air Systems Command (NAVAIRSYSCOM). Naval aviation facility requirements are driven by a multitude of Navy and Marine Corps aircraft, weapons system, airborne electronics systems and related ground-based aeronautical equipment, training, and material support. NAVAIRSYSCOM works with the respective program entities to identify unique aviation and operational support facilities requirements. As the Navy lead field activity for national airspace system modernization, NISE-EAST is responsible for planning and management support for worldwide Navy and Marine Corps ATC, NAALS community in the areas of radar air traffic control facilities/center and fleet area control and surveillance facilities (FASFAC) design and installation and air-to-ground/crash/landline communication system modernization. Responsibilities include radar air traffic control facility (RATCF) electronic system design, engineering, and installation including instrument flight rules (IFR) room, control tower cabs, FASFAC, airport surveillance radar (ASR), precision approach radar (PAR), air traffic control radar beacon system (ATCRBS), radar ranges, communication control systems, radar video display systems, HF/UHF/VHF air-to-ground communications systems, microwave systems, fiber optic systems, flight data transmission systems and ancillary equipment when being installed as an integrated system. Naval Command, Control and Ocean Surveillance Center In-Service Engineering (NISE), West Detachment, Vallejo, CA is responsible for facility electronic system design, engineering, and installation for stand-alone Navy ATC NAALS installation. NAVAIRSYSCOM has fiscal authority, program management authority

MIL-HDBK-1024/1

and material support responsibility for Navy and Marine Corps NAALS and associated equipment for use on naval shore aviation facilities.

1.3.4 Space and Naval Warfare Systems Command (SPAWARSYSCOM).

SPAWARSYSCOM exercises technical control of design, development, procurement, and installation of the electronic equipment for an electronic facility at a shore activity. SPAWARSYSCOM provides technical guidance and direction in shore electronic engineering from project inception to completion, except in special cases where the electronic systems or equipment is specifically assigned to another command.

1.3.5 Maintenance Authority. SPAWARSYSCOM exercises technical control through regional and district offices, whose responsibilities include installation and maintenance engineering of electronic equipment that is beyond the capacity of station forces. Regional and district offices represent SPAWARSYSCOM for electronic engineering control during facility design development. NISE-EAST represents NAVAIRSYSCOM for electronic engineering control and development of ATC electronic facilities design of RATCFs. In a similar capacity, NISE West Detachment Vallejo is responsible for developing electronic facilities design for Navy ATC NAALS and related equipment.

1.3.6 Designer. The designer (planner, engineer, and architect) enters design development at the predesign programming stage and after the operational requirements have been established. The designer plans the facility to satisfy the operational requirements set forth in this handbook, MIL-HDBK-1024/1, and in the BESEP, IDSEP, and BEAP, and prepares project drawings and specifications under the control of NAVFAC and the guidance of SPAWARSYSCOM. Requirements for projects that do not directly involve electronic equipment may not require a BESEP. While maintaining close liaison with the NAVFAC command responsible for the project, the designer is responsible for coordinating technical matters with the sponsors and users of the project.

1.3.6.1 Base Electronic Systems Engineering Plan (BESEP). The BESEP is primarily a technical planning and management document, with sufficient installation detail provided to enable evaluation of operational impact (signal flow, site, etc.) on user activities. It is a basic technical document governing electronics and other affected phases of shore electronics planning and implementation. It translates a sponsor or user statement of operational need, which shall be referenced in the BESEP, into a technical description of shore electronics systems and facilities required to meet this need. It provides required information on electronic systems, equipment and devices to be used, their pertinent technical parameters, physical characteristics, environmental and interface requirements, and system performance objectives. The BESEP identifies the minimum installation criteria (red/black ground system, etc.) to be applied. Methods of verifying systems performance and compliance with identified installation requirements

MIL-HDBK-1024/1

are included. See SPAWARS Instruction 2804.1, Policy and Procedures Concerning Base Electronic Systems Engineering Plan.

1.3.6.2 Intrusion Detection Systems Engineering Plan (IDSEP). NISE-EAST is directed by Commander Naval Investigative Service Command (COMNISCOM), OP-09, to prepare IDSEPs for electronic sensor system (ESS)/intrusion detection system (IDS) installations when a MILCON is required. The reference document for the IDSEP is Section 6.0 of SPAWARS Instruction 2804.1 and is equivalent to a MILCON BESEP. The scope of the IDSEP is specific only to detailed requirements for design of the facility in order to accommodate ESS/IDS and related electronic equipment.

1.4 Policy Statement. Design of aviation operational and support facilities should be based on operational requirements and guidance contained in this handbook, MIL-HDBK-1024/1. Operational facilities should incorporate the user's requirements, provide the most effective support possible, and accommodate the best safety, habitability, energy conservation, maintenance, and training characteristics. Operational requirements should take precedence over other criteria such as convenience or cost should compromises be required. Documents such as the BESEP, applicable NAVFAC publications, and other pertinent Navy and DOD documents shall be governing sources for establishment of requirements.

MIL-HDBK-1024/1

## Section 2: GENERAL DESIGN CRITERIA

2.1 Facility Planning. Plan for the design and construction of facilities discussed herein in accordance with NAVFAC P-80, Facility Planning Criteria for Navy and Marine Corps Shore Installations, MIL-HDBK-1190, Facility Planning and Design Guide, and NAVFAC Instruction 11010.44, Shore Facilities Planning Manual.

2.2 Site Considerations

2.2.1 Site Suitability. Basic considerations for site selection include terrain characteristics and meteorological conditions. Locate facilities requiring technical adequacy for radiation, reception, visibility, etc., following the requirements established by the governing agency or command responsible for the project. Ensure site selection considerations are fully understood and incorporated into the design. Site considerations for electronic facilities are contained in MIL-HDBK-1012/1, Electronic Facilities Engineering.

2.2.2 Separation of Structures. Comply with MIL-HDBK-1008, Fire Protection for Facilities Engineering, Design, and Construction for separation of structures.

2.2.3 Access and Parking. Provide paved access drives and parking lots for attended facilities in accordance with NAVFAC DM-5.04, Pavements. Access drives and parking facilities for unattended facilities may be gravel or crushed shell except where access to the facility is from runways and taxiways. In these cases, pave a sufficient portion of the access drives and parking lots to avoid the scattering of gravel onto the operational surfaces. At facilities adjacent to runways and taxiways, provide parking space off the operational surface for a maintenance vehicle. Locate the parking space to avoid interference with the operation of any facilities in the area. Ensure roadway and vehicle parking surfaces within the airfield operations area are flush with the surrounding ground surface.

2.2.3.1 Parking. The number of parking stalls required at each facility varies dependent upon the function, location, and size of the user command. Consider double work shifts and shift changes when determining the required number of parking stalls. Criteria for establishing the required number of parking stalls based on the type of facility and size of the work force are provided in MIL-HDBK-1190. Provide geometric layout and design for parking lots and stalls in accordance with Army TM 5-822-2/Air Force Manual 88-7, Chapter 5, General Provisions and Geometric Design for Roads, Streets, Walks, and Open Storage Areas, and NAVFAC Definitive Drawing No. 1404837, Parking Area Criteria for Vehicles. In addition to requirements established in these reference documents, conform to the following restrictions:

a) Parking of privately owned vehicles (POV's) within level three and level two restricted areas is prohibited.

MIL-HDBK-1024/1

b) Parking of POV's within 15 feet of any building is prohibited.

c) Parked vehicles within either the 20-foot minimum outside security zone or the 30-foot minimum inside security zone associated with restricted area security fencing is prohibited.

2.2.3.2 Access for Fire Department Apparatus. Consult local authorities having jurisdiction for criteria regarding access to the area and clearance around the buildings for fire apparatus maneuvering. The equipment expected to respond to an emergency will control these decisions. See National Fire Protection Association (NFPA) 1141, Fire Protection in Planned Building Groups.

2.2.4 Site Drainage. Provide drainage design in accordance with MIL-HDBK-1005/3, Drainage Systems. Metallic pipe and reinforced concrete pipe are inappropriate at some sites. Establish requirements for use of metallic pipe and reinforced concrete pipe early in facility planning. Consider drainage swales with minimal velocities to avoid damage of ground planes. Do not use storm drain pipes through an antenna ground plane. Refer to MIL-HDBK-1012/1.

2.2.5 Protection of Fixed Objects. Provide barriers to protect electrical transformers, generators, fuel tanks, fire hydrants, etc., from damage due to vehicles and moving equipment.

2.2.6 Airfield Safety. Consider safety clearances when siting facilities in or near aviation operational areas. Refer to NAVFAC P-80.3, Facility Planning Factor Criteria for Navy and Marine Corps Shore Installations, Appendix E: Airfield Safety Clearances and Title 14, CFR Part 77, Objects Affecting Navigable Airspace. Objects located within runway clear zones shall be fabricated for low impact resistance in accordance with FAA Engineering Report ER-530-81-04, Structural/Mechanical Design Requirements for Low Impact Resistance for Microwave Landing System Structures (MLS/LIRS). Objects penetrating the airspace surfaces described in NAVFAC P-80.3 and Title 14, CFR Part 77 require a waiver of clearance criteria. The point of contact for waiver of Navy criteria is NAVAIRSYSCOM, Code AIR-09Y1. The point of contact for waiver of FAA criteria is the Chief, Air Traffic Division of the FAA Regional Office having jurisdiction over the area within which the construction will be located. Provide obstruction marking or lighting for facilities located in or near aviation operational areas in accordance with FAA Advisory Circular AC 70/7460, Obstruction Marking and Lighting.

2.2.6.1 Objects Located on Airfield. Location of any objects within airfield clear zones and/or airspace surfaces will be made by NISE-EAST with NAVAIRSYSCOM concurrence.

2.2.6.2 Objects in Violation of Airfield Safety Criteria. Objects that must be located in violation of NAVFAC P-80 and NAVFAC P-80.3 criteria shall be located to result in the minimum violation possible compatible with the

MIL-HDBK-1024/1

function of the object. Construct objects in violation of NAVFAC P-80 and NAVFAC P-80.3 with lightweight and low impact resistant materials in accordance with FAA ER-530-81-04. Ensure footings and bases for such objects are flush with the ground surface and the height of the object is the minimum necessary. A waiver request indicating key points of contact, along with the associated BESEP, shall be submitted to NAVAIRSYSCOM, Code AIR-09Y1 for any facility in violation of any NAVFAC airfield safety criteria.

2.3 Architectural and Structural Requirements. Place design emphasis on fire resistance, minimal maintenance and repair cost, and ease of facility expansion or modification. Electronic communications equipment housed in the building varies with the mission of the installation. Design facility exterior in accordance with the BEAP or local command architectural guidance.

2.3.1 Acoustics. Provide means to manage building acoustics by proper selection of construction assemblies and finishes. Refer to pages 4.7 through 4.45 of Time Saver Standards for Architectural Design Data and NAVFAC DM-1.03, Architectural Acoustics. Analyze and control the acoustical properties of construction assemblies by modifying room acoustics through control of reverberation (absorption) and attenuating structure-borne sound from exterior sources, interior sources between rooms, and equipment generating sound (isolation). Provide the following room noise levels:

<u>Area</u>	<u>Room Criteria (RC)</u>
Air Traffic Control Operations and Instrument Flight Rules Control, Conference, Training, Projection, and Bunk Rooms	30
Private Offices	35
Open Offices, Lobbies, Ready Rooms and Waiting Areas	40
Restrooms, Corridors, Computer and Electronic Equipment Rooms	45
Cargo and Materials Handling and Vehicle Areas, Mechanical, Electrical, and Generator Rooms, Remote and Unattended Facilities	50

2.3.2 Handicapped Employees. Provide barrier-free access to civilian work spaces and other spaces intended for public access. Design facilities to locate handicapped access spaces on first floor only unless the size of the facility's administration and other accessible areas requires a second floor. Areas hazardous to handicapped persons need not be accessible. Comply with current criteria in Uniform Federal Accessibility Standards (UFAS). Refer to MIL-HDBK-1190.

MIL-HDBK-1024/1

2.3.3 Structural Design. Design in accordance with MIL-HDBK-1002 series, Structural Engineering. Base an economical structural system on facility size, projected load requirements, quality of local available materials, local labor and construction materials, and local wind, snow, seismic, geologic, and permafrost conditions. Design structural systems to support roof-mounted and/or suspended loads, when required.

2.3.3.1 Lateral Loads. Design buildings and towers (antenna supports) to withstand wind and seismic loads appropriate to the region in which they are to be constructed. Refer to MIL-HDBK-1002/2, Structural Engineering - General and NAVFAC P-355, Seismic Design for Buildings. Seismic analysis of Government-furnished buildings and antenna supports is not required.

2.3.3.2 Antenna Supports. Before undertaking unique antenna support designs, consider the use of existing commercial products suitable for the purpose. Navy standard designs for UHF/VHF and ASR antenna supports are available. See Figure 1 and Figure 2.

2.3.4 Construction Materials. Design attended facility buildings using styles and materials as approved by the ordering authority. Unless otherwise directed, design unattended facility buildings using concrete, concrete masonry, pre-engineered metal, or premanufactured metal or fiberglass-reinforced plastic. NAVFAC policy requires materials, equipment, and construction methods that provide maximum overall economy consistent with functional and aesthetic requirements, reasonable comfort, and sound architectural and engineering practices. Materials, equipment, and methods used should result in low costs consistent with economic maintenance for the required use and life expectancy of the facility. Refer to MIL-HDBK-1001/2, Materials and Building Components.

2.3.4.1 Reflective Surfaces. To prevent mirrorlike reflections from building surfaces to aircraft in flight, provide roofs and other external surfaces with a specular reflectance compatible with the location of the building on the airfield. If the building is so located that glare may be an operational hazard, provide the critical surfaces of that building with a light reflectance of not more than 10, measured at an angle of 85 degrees in accordance with American Society for Testing and Materials (ASTM) D 523, Standard Test Method for Specular Gloss.

2.3.5 Floors. Construct ground level floors with reinforced concrete on a compacted subgrade in accordance with MIL-HDBK-1001/2. Elevated floor systems are directly related to the type of structural system selected. Ensure the finished floor elevation is at least 4 inches above the adjacent site finished grade elevation.

MIL-HDBK-1024/1




Figure 1  
Radio Antenna Tower

MIL-HDBK-1024/1




Figure 2  
ASR Antenna Tower

## MIL-HDBK-1024/1

2.3.5.1 Permanent Floors. Consider the placement of cables and wiring for electronic equipment when selecting floor construction. Install an equipotential plane conforming to MIL-HDBK-419, Volume 1, Grounding, Bonding, and Shielding for Electronic Equipment and Facilities Applications, in the floor of electronic facility spaces. The preferred method of placing cables and wiring is given in the BESEP for the facility.

2.3.5.2 Access Flooring. Provide access flooring to meet the requirements of NFPA 75, Protection of Electronic Computer/Data Processing Equipment, Military Specification MIL-F-29046, General Specifications for Raised Flooring, and MIL-HDBK-1008. Provide a bolted grid (stringer) or a rigid grid system. Provide seamless vinyl or laminated plastic finishes. Keep air supply panels and similar inserts flush with the flooring surface. Specify installation procedures to conform with MIL-HDBK-419, Volumes 1 and 2. Provide depressed structural framing and slabs in areas where access flooring occurs to result in uniform, continuous finish floor levels between adjacent floor spaces. Provide a raised floor installation above a level permanent floor when it is not economical or practical to depress the structural framing and slab. Refer to NAVFAC guide specification NFGS-10270, Access Flooring.

2.3.6 Roofing. Provide roof system and insulation to meet the requirements of MIL-HDBK-1001/5, Roofing and Waterproofing. Determine thermal resistance of roof insulation by design criteria and life cycle costs. Refer to American Society of Heating, Refrigerating and Air Conditioning Engineers (ASHRAE), Handbook Fundamentals, NAVFAC P-442, Economic Analysis Handbook, and TM 5-802-1, Life Cycle Cost Analysis Handbook.

### 2.3.7 Walls

2.3.7.1 Thermal Insulation and Vapor Retarders. Locate vapor retarders with care in view of the thermal differentials associated with buildings. Do not use vinyl wall covering and impervious paint in the interior surface of exterior walls in humid areas (as defined in MIL-HDBK-1190) unless calculations show that condensation will not occur in the wall. Special purpose rooms such as computer rooms normally require stringent air conditioning requirements. Provide adequate insulation and vapor transmission barriers to minimize the loads on the mechanical system. Properly insulate ceiling decks of spaces below supercooled computer rooms and perimeter walls to prevent condensation.

2.3.7.2 Exterior Walls. Construct exterior walls of concrete (cast-in-place or precast), brick, concrete masonry units, or other system appropriate to the structural system and the function of the building. If concrete masonry units are used for exposed exterior surfaces, provide coatings on exterior masonry surfaces to prevent moisture penetration above and below grade. Provide insulation in exterior walls to meet the criteria for types and thermal properties in accordance with the appropriate section of MIL-HDBK-1001/2. Refer to NFGS-04200, Unit Masonry and NFGS-03300, Cast-in-Place Concrete.

## MIL-HDBK-1024/1

2.3.7.3 Interior Walls. Construct interior walls of concrete masonry or gypsum wallboard on metal studs. Provide moisture resistant gypsum wallboard when used in restroom and showers. Refer to NFGS-09250, Gypsum Board. Provide fire-rated interior walls in accordance with MIL-HDBK-1008 and NFPA 101, Life Safety Code.

2.3.8 Interior Finishes. Refer to MIL-HDBK-1001/2. Provide interior finishes in accordance with pars. 2.3.8.1 through 2.3.8.10. Coordinate interior finishes with the user.

2.3.8.1 Sealed Concrete Floors. Provide sealed concrete floors for remote and unattended facilities, mechanical, electrical, and janitor rooms, cargo and materials handling, and vehicle parking areas. Refer to NFGS-03300.

2.3.8.2 Resilient Flooring. Provide resilient flooring for administrative, training, conference, lobby, ready rooms, bunk, restroom (remote buildings only), and similar spaces. Refer to NFGS-09660, Resilient Tile Flooring and NFGS-09665, Sheet Vinyl Flooring.

2.3.8.3 Ceramic Tile Flooring. Provide ceramic tile flooring for restroom and showers. Refer to NFGS-09310, Ceramic Tile, Quarry Tile, and Paver Tile.

2.3.8.4 Carpet Flooring. Provide carpet for office, computer, and similar spaces. Provide anti-static carpet for electronic equipment areas. Refer to NFGS-09680, Carpet.

2.3.8.5 Masonry Finish Walls. Consider exposed masonry walls for remote and unattended facilities, mechanical, electrical, and janitor rooms, cargo and materials handling, and vehicle parking areas. Coordinate requirements for painted walls with facility user. Refer to NFGS-09900, Painting.

2.3.8.6 Painted Finish Walls. Provide painted walls for administrative, training, conference, computer, lobby, ready rooms, bunk, restrooms, and similar spaces. Refer to NFGS-09900.

2.3.8.7 Ceramic Tile Finish Walls. Provide a ceramic tile wall finish for shower rooms. Refer to NFGS-09310.

2.3.8.8 Exposed Structure Ceilings. Provide exposed structure ceilings for remote and unattended facilities, mechanical, electrical, and janitor rooms, cargo and materials handling, and vehicle parking areas.

2.3.8.9 Acoustical Tile Ceilings. Provide non-combustible acoustical tile ceilings in administrative, training, conference, computer, lobbies, bunks, ready rooms, and similar spaces. Provide moisture resistant ceiling tile in restrooms. Refer to NFGS-09500, Acoustical Treatment.

2.3.8.10 Shower Ceilings. Provide veneer plaster on moisture resistant gypsum wallboard or gypsum plaster on metal lathe ceilings in showers. Refer

## MIL-HDBK-1024/1

to NFGS-09100, Metal Support Systems, NFGS-09200, Lathing, NFGS-09212, Plastering and Stuccoing, and NFGS-09215, Veneer Plaster.

2.3.9 Doors. Provide doors and door hardware in accordance with pars.

2.3.9.1 through 2.3.9.8. Refer to Military Bulletin MIL-BUL-34, Engineering and Design Criteria for Navy Facilities. Provide fire-rated doors in accordance with NFPA 80, Fire Doors and Windows and NFPA 101.

2.3.9.1 Exterior Doors. Provide insulated, self-closing, swinging exterior steel doors with steel frames. Provide storefront type entrances with steel or aluminum framing at main building entrances. Provide heavy-duty doors and door hardware in flightline areas.

2.3.9.2 Interior Doors. Provide heavy-duty, self-closing, swinging interior doors.

2.3.9.3 Overhead Doors. Provide manually or electrically operated overhead doors. Refer to NFGS-08331, Rolling Service and Fire Doors and NFGS-08360, Sectional Overhead Doors. Provide electrically operated overhead doors with limit switches and provision for manual operation. Control doors by momentary contact type push buttons located near the door. Install safety devices to prevent injury to personnel and equipment. Insulate overhead doors and provide bottom waterproof seal and weatherstripping. Do not use rolling doors to enclose heated spaces. Consider vertical lift or folding doors to enclose heated spaces when sectional doors are not appropriate. Refer to NFGS-08367, Vertical Lift Metal Doors.

2.3.9.4 Door Hardware. Refer to NFGS-08710, Finish Hardware. Consult public works and base fire departments for exterior hardware required for access to mechanical rooms, electrical rooms, sprinkler control rooms, and fire alarm annunciator panels. Do not provide hardware on the exterior of emergency exit doors.

2.3.9.5 Hinges. Provide heavy-duty stainless steel hinges, minimum 1-1/2 pair per door leaf. Provide ball-bearing type for doors with closers or subject to high use, and non-removable pins for exterior doors.

2.3.9.6 Locksets. Provide heavy-duty cylindrical type locksets with minimum six-pin cylinders. Provide electronic cipher door locks at secured locations indicated. Review keying system with the user and provide type required (master, grandmaster or great-grandmaster), either new or integrated with user's existing system.

2.3.9.7 Exit Devices (Panic Hardware). Provide single exit doors with locksets in lieu of double doors with exit devices (panic hardware) unless exit devices are required by NFPA 101. Provide a removable mullion (vertical divider member) with a pair of rim-type exit devices for exterior double doors when single doors are not feasible.

MIL-HDBK-1024/1

2.3.9.8 Closers. Comply with manufacturer's recommendations for size of door control unit depending on size of door, exposure to weather, and anticipated frequency of use. Where parallel arms are indicated for closers, provide closer unit one size larger than recommended for use with standard arm. Hold-open devices are not permitted.

2.3.10 Windows. Provide weatherproof and stain resistant, aluminum-framed (steel-framed for industrial type facilities), factory finished windows. Provide exterior windows with insulated glazing where required for noise, thermal or solar protection. Provide tinted glazing for solar protection. Provide glazing, window frames, and frame anchors to withstand the required wind pressures. Refer to NFGS-08510, Steel Windows, NFGS-08520, Aluminum Windows, NFGS-08529, Aluminum Storm Windows, and NFGS-08800, Glazing. Install windows in fire-rated partitions in accordance with NFPA 80.

2.3.10.1 Service Windows. When located in fire-rated partitions, provide fire-rated service windows or service windows with automatic fire shutters. Refer to NFPA 80 and NFPA 101.

2.3.11 Ladders. Design ladders in accordance with American National Standards Institute ANSI A14.3, Safety Requirements for Fixed Ladders. Provide fall protection and safety devices in accordance to ANSI A14.3.

2.3.12 Pre-engineered, Premanufactured Buildings. Consider pre-engineered metal or premanufactured metal or fiberglass-reinforced plastic buildings for remote and unattended facilities and for temporary construction. See Figure 3.

## 2.4 Mechanical Engineering

2.4.1 Energy Conservation. Design climate-controlled facilities for energy efficiency. Consider isolated ventilation or air conditioning systems for equipment with high heat loads or that require more critical temperature or humidity control than would otherwise be required for the remainder of the occupancy.

2.4.2 Equipment Selection. Select adequately sized air conditioning equipment for personnel comfort applications to remove the sensible and latent heat loads generated within these areas. Computer rooms and electrical equipment rooms produce predominantly sensible heat and require specially designed units. Refer to MIL-HDBK-1012/1. Ensure mechanical systems do not interfere with electronic equipment or radiated signals.

2.4.3 Heating and Air Conditioning. Provide heating and air conditioning in accordance with NAVFAC DM-3.03, Heating, Ventilating, Air Conditioning and Dehumidifying Systems, MIL-HDBK-1190, and MIL-HDBK-1012/1. Provide duct smoke detectors and controls in accordance with MIL-HDBK-1008.

MIL-HDBK-1024/1




Figure 3  
Prefabricated Building

MIL-HDBK-1024/1

2.4.4 Ventilation. Refer to MIL-HDBK-1012/1, NAVFAC DM-3.03, and NAVFAC DM-28.04, General Maintenance Facilities. Design ventilation systems in accordance with the following:

a) Provide outside air ventilation requirements in accordance with ASHRAE Standard 62, Ventilation for Acceptable Indoor Air Quality and MIL-HDBK-1012/1.

b) Ensure restroom facilities are exhausted at a minimum of 2 cfm/square feet and not less than 25 cfm total. Provide exhaust fans which operate when restroom is occupied. Interlock exhaust fan with light switch for restrooms equipped with dedicated exhaust systems.

c) Do not provide exhaust fans for the ventilation of electronic equipment rooms. Accomplish ventilation through the use of thermostatically controlled intake fans providing a filtered air supply to the equipment room. Maintain positive air pressure in electronic equipment rooms to reduce the infiltration of dust and other foreign matter through door jambs and other openings. Consider high efficiency (60 to 90 percent) filtration where dust and other particulate/pollution can cause malfunctioning of equipment. When intake air is from a salt-laden environment, route intake air through the dehumidifying system to remove moisture suspended salts.

d) Ventilate uninterrupted power supply (UPS) rooms in accordance with MIL-HDBK-1012/1.

2.4.4.1 Battery Shops. Provide recessed air supply and exhaust vents in the ceiling of lead acid and nickel-cadmium battery shops. Slope the ceiling surface to provide a single high point at the exterior wall of the building. Locate the exhaust vent at the highest ceiling point and discharge the exhaust through the exterior wall. Do not recess other items in the battery shop ceilings. Design battery shop ventilation systems in accordance NFPA 70, National Electrical Code and the following:

a) Provide one air change per hour for nickel-cadmium battery shops. Increase the air change rate when outdoor air can be used to limit the shop temperature to 85 degrees F.

b) Provide three air changes per hour for lead acid battery shops. Increase the air change rate when required for mechanical ventilation cooling. Provide a non-sparking wheel and locate the fan motor out of the air stream. Design the ventilation system to provide negative static pressure by exhausting 10 percent more air than supplied. Provide 100 percent outside air supply.

2.4.5 Outside Weather Conditions. Obtain summer and winter outside weather conditions from NAVFAC P-89, Engineering Weather Data, or ASHRAE Handbook of Fundamentals.

MIL-HDBK-1024/1

## 2.4.6 Inside Design Conditions

### 2.4.6.1 Personnel Comfort. Provide the following:

Cooling	75 to 78 degrees F dry bulb 50 percent relative humidity (minimum)
Heating	68 degrees F (minimum)

2.4.6.2 Computer and Electronic Rooms. Maintain computer and electronic spaces at a year-round temperature of 70 to 74 degrees F and relative humidity of 40 to 50 percent. Consult the facility BESEP for specific requirements. Individual equipment may require less restrictive space conditions. In this case, the least restrictive condition should be used.

2.4.6.3 Storage Areas. Maintain storage areas at 40 degrees F minimum to prevent freezing.

2.4.7 Plumbing. Provide plumbing for facilities in accordance with NAVFAC DM-3.01, Plumbing Systems. Ensure that plumbing work not covered by Navy criteria meets the requirements of the National Plumbing Code Handbook.

2.4.7.1 Battery Shops. Provide the following in lead acid and nickel-cadmium battery shops:

- a) Acid and alkali resistant floor drains.
- b) Emergency shower and eyewash facilities within 25 feet of the battery handling areas. Provide potable water for the showers and eyewash stations. Provide a collection, holding, and treatment system for the shower wash water before it is discharged into the sanitary sewer.
- c) Acid and alkali resistant dump sinks. Provide separate, gravity operating, collection, holding, and treatment system for each type of waste. Do not discharge acid or alkali waste into the sanitary sewer system.
- d) Acid and alkali resistant base cabinet sinks.
- e) Hose, hose bibbs, and hose rack for flushing neutralized spilled electrolytes.
- f) Acid and alkali resistant spill containment system with sufficient volume to contain 110 percent of the largest electrolyte container or battery plus water for flushing neutralized spilled electrolyte.

2.4.8 Water and Sanitation. Unattended facilities are not normally provided with water and sanitation facilities (sink and toilets). However, provide water and sanitary facilities at unattended facilities where a significant amount of maintenance is anticipated and sanitary facilities are

MIL-HDBK-1024/1

not available in the vicinity. Consider the use of chemical toilets and bottled water.

#### 2.4.9 Fire Protection

2.4.9.1 Electronic Equipment Areas. Design per MIL-HDBK-1008. Within buildings protected by an automatic sprinkler system, provide a preaction system in areas having mission essential or high monetary value electronic equipment. Provide automatic and manual actuation of the preaction system. Provide controls to discontinue electric power to electronic equipment upon water flow. Provide manual disconnect of electric power to air traffic control equipment. Provide separation from other areas with fire-rated partitions. Provide smoke detection, at ceilings and in sub-floor areas, connected to building fire alarm system. Refer to par. 2.5.10. Areas containing only word processing equipment and personal computers are not within the scope of this paragraph.

2.4.9.2 Emergency Generator Protection. Refer to MIL-HDBK-1008.

2.4.9.3 Portable Fire Extinguishers. Provide portable fire extinguishers for facilities in accordance with MIL-HDBK-1008.

2.4.9.4 Underfloor Spaces. Provide types of cable which allow exclusion of fixed extinguishing systems. Refer to MIL-HDBK-1008.

2.4.9.5 Automatic Sprinkler Systems. Provide automatic sprinkler systems in accordance with MIL-HDBK-1008. Install sprinkler systems in accordance with NFPA 13, Installation of Sprinkler Systems.

2.4.9.6 Standpipe System. Refer to MIL-HDBK-1008 for standpipe system requirements.

2.4.9.7 Halon Fire Protection Systems. The use of Halon is not permitted.

2.4.9.8 Hydrants. Provide hydrants and required water supply. Consider eliminating fire hydrants at remote and unattended facilities. Consult public works and base fire departments for requirements. Refer to MIL-HDBK-1008.

2.4.9.9 Elevators. Provide fire protection criteria for design and construction of elevators in accordance with subpars. a) through e) below, ANSI A17.1, Safety Code for Elevators and Escaltors, and NFPA 13. If there is a conflict of criteria, subpars. a) through e) take precedence over NFPA 13 and ANSI A17.1.

a) Provide wet-pipe, intermediate temperature automatic sprinkler heads in the elevator pit. (Note: intermediate temperature sprinkler heads are in the 175 to 225 degrees F range, with the preference being 212 degrees F). Ensure the operation of sprinklers in the pit does not cause shutdown of the main power supply to the elevators.

## MIL-HDBK-1024/1

b) Provide wet-pipe, intermediate temperature (preference being 212 degrees F) automatic sprinkler heads in the elevator machine room. Provide a control valve, check valve, and a water flow switch in the branch line supplying the sprinklers in the elevator machine room. Locate the control valve, check valve, and water flow switch in an accessible location outside the elevator machine room. Provide a water flow switch that, when activated, causes the main power supply to elevators controlled from that elevator machine room to be automatically disconnected with no time delay.

c) Automatic sprinklers are not required at the top of the elevator hoistway except where a roped hydraulic or a holeless hydraulic elevator has been installed, or where a hydraulic elevator's pressurized supply line runs at points above the first landing level. If automatic sprinklers are installed at the top of the elevator hoistway, their activation does not require shutdown of the main power supply to the elevators.

d) Provide a warning light and an audible signal in the cab of each elevator. Ensure the warning light is a minimum of 3 inches in height and 4 inches in width. Mount the warning light prominently in, above or adjacent to the car's operating panel. Do not obscure the light by the elevator's protective pads. Provide a warning light that cannot be read when not illuminated. When illuminated, the warning light reads: "DANGER! FIRE!" "EXIT THE ELEVATOR NOW." Provide an audible alarm, such as a bell, buzzer or electronic tone, that is louder than any other audible signal being used in the cab. Supply power to both the warning light and the audible warning device from the elevator's main controller.

e) Activate the warning sign and audible warning device simultaneously by a 135 degree F, rate-compensated heat detector mounted in the elevator machine room. Mount the heat detector adjacent to the sprinkler head, or equidistant between sprinkler heads when there is more than one sprinkler head in the elevator machine room. Do not connect the heat detector to the building's fire alarm system.

2.4.10 Noise and Vibration Control. Design mechanical systems and equipment to limit noise and vibration in accordance to NAVFAC DM-3.10, Noise and Vibration Control for Mechanical Equipment.

## 2.5 Electrical Engineering

2.5.1 General Requirements. Design in accordance with MIL-HDBK-1004 series, Electrical Engineering. Ensure electrical work not covered by Navy criteria meets requirements of NFPA 70.

2.5.2 Distribution Panels. Install distribution panels for technical use in electronic equipment rooms and other spaces containing technical equipment.

## MIL-HDBK-1024/1

2.5.3 Incoming Power. Provide incoming power through an isolation transformer and an entrance switch. Provide power to only one facility through the isolation transformer. Distribute power to an essential and non-essential bus, if required. Connect the emergency generator, if required, to the essential bus through an isolation switch and automatic switch gear. Provide either single or three phase power as required.

2.5.4 Separate Buses. Provide electrical power for electronic, air traffic control, computer, and other technical equipment on a separate bus from electrical power for facility mechanical and building systems.

2.5.5 Lightning Protection. Design facilities for lightning protection. Refer to NFPA 78, Lightning Protection Code, and MIL-HDBK-1004/6, Lightning Protection, for minimum standards.

2.5.6 Lighting. Design lighting in accordance with MIL-HDBK-1190. Consider natural lighting sources.

2.5.6.1 Interior Lighting. Provide fluorescent interior lighting with radio frequency shielding and suppression filters. Calculate lighting levels using zonal cavity method.

2.5.6.2 Exterior Lighting. Provide high pressure sodium vapor exterior lighting. Calculate lighting levels using point-by-point method.

2.5.7 Emergency Electrical Power

2.5.7.1 Emergency Generator. Provide emergency generators with electronic line monitoring equipment and automatic starting and switching capability. When used in conjunction with an UPS, provide generator output at least 1.5 times the output rating of the UPS. Ensure emergency generator is capable of supplying the rated load within 15 seconds of a power failure. Provide the following for emergency generators:

a) An isolation switch to bypass the emergency generator during generator maintenance.


b) An automatic battery charger for maintenance of generator starting batteries.

c) An isolated mounting slab for the generator to reduce noise and vibration transmission.

d) See Figure 4. Provide the following when an indoor emergency generator is required:

(1) A separate generator room with an independent ventilation system.

MIL-HDBK-1024/1



MIL-HDBK-1024/1

(2) An engine exhaust system connected to the exterior of the facility with an exterior muffler. Configure the exhaust system to prevent rainwater or condensation from entering the engine manifold.

(3) Adequate engine cooling by a radiator duct or externally mounted radiator.

Consider a premanufactured building to house an indoor generator. See Figure 5. Consider an outdoor unit in mild climate conditions. Consider a below ground generator vault for units which shall be sited within airfield clear zones or primary surfaces.

2.5.7.2 Emergency Generator Fuel Storage. Design fuel storage for diesel or jet fuel powered generators in accordance with NAVFAC DM-22, Petroleum Fuel Facilities, state and local regulations, and the following:

a) Above Ground Storage Tanks: Title 40, CFR Part 112, Oil Pollution Prevention; Title 40, CFR Part 113, Liability Limits for Small Onshore Storage Facilities, Subpart A, Oil Storage Facilities; and Title 40, CFR Part 114, Civil Penalties for Violation of Oil Pollution Prevention Regulations.

b) Underground Storage Tanks: Title 40, CFR Part 280, Underground Storage Tanks Technical Requirements.

Provide fuel storage capacity for 24 hours of continuous generator operation. Provide separation between fuel storage tanks and adjacent buildings, parking aprons, and property lines in accordance with NAVFAC DM-22. Provide double wall storage tanks and piping.

2.5.8 Uninterrupted Power Supply (UPS). Provide an UPS in electronic facilities and air traffic control installations for critical technical loads and the specific requirements of the ordering authority. The UPS will be government furnished. Install the UPS in accordance with MIL-HDBK-1004/1, Electrical Engineering - Preliminary Design Considerations and MIL-HDBK-1012/1.

2.5.9 400-Hertz (Hz) Power. When required by the ordering authority, provide 400-Hz solid state converter in accordance with NFGS-16306, 400-Hertz (Hz) Solid State Frequency Converter. Design in accordance with MIL-HDBK-1004/5, 400-Hz Medium-Voltage Conversion/Distribution and Low-Voltage Utilization Systems. De-rate 400-Hz cables and locate in separate non-magnetic raceway system. Refer to MIL-HDBK-1012/1.

MIL-HDBK-1024/1




Figure 5  
Prefabricated Indoor Emergency Generator Room Layout

MIL-HDBK-1024/1

2.5.10 Fire Alarm and Detection Systems. Provide fire alarm and detection system capable of providing maximum protection for personnel, equipment and buildings. Refer to MIL-HDBK-1008 for design criteria and application requirements. Include a master fire control panel monitoring the different fire zones of the facility. Install fire alarm and detection system in accordance with NFPA 101.

2.5.10.1 Signal Transmission. Provide fire alarm and detection systems which transmit the following signals:

a) Local Signal. Sounds local alarm to permit occupants to initiate first aid fire fighting and/or to evacuate.

b) Remote Signal. Transmits alarm to fire department or other designated central alarm location to implement emergency action.

c) System Signal. Activates automatic fire extinguishing systems where appropriate. Provide automatic extinguishing systems with equipment to transmit local and remote signals when the system activates.

2.5.10.2 Electronic Equipment Spaces. Provide smoke detection systems in electronic equipment areas to transmit local and remote signal as well as activate extinguishing system where provided. Include automatic supervision of alarm circuits. Provide manual fire alarm systems capable of transmitting the same signals. Areas containing only word processing equipment and personal computers are not within the scope of this paragraph.

2.5.10.3 Raised Floor Cable Spaces. Provide automatic detection systems per MIL-HDBK-1008.

2.5.10.4 Remote and Unattended Facilities. Provide manual and automatic fire alarm and detection systems at remote and unattended facilities. Provide local and remote signaling systems.

2.5.10.5 Occupied Buildings. Provide occupied buildings with fire alarm and detection systems per MIL-HDBK-1008. Follow par. 2.5.10.2 for occupied buildings which house electronic equipment.

2.5.11 Communications Systems. Provide voice, data, and equipment control communications systems in accordance with MIL-HDBK-1004/7, Wire Communications and Signal Systems. Consider fiber optic systems in facilities requiring extensive internal communications systems for electronic equipment.

## 2.6 Physical Security

2.6.1 General Requirements. Physical security is concerned with limiting, controlling, or preventing personnel access to specific areas. A sound physical security program is the result of good planning. The best and most economical programs are those incorporated in the facility's design and

MIL-HDBK-1024/1

construction. The facility configuration and location; the use of barriers, protective lighting, type of construction, IDS, closed circuit television (CCTV), and security fencing; and the guard communication network shall be coordinated with the user to ensure conformance with the installation security plan. The mode of operation, level of security, and designer's responsibility for particular security elements will be designated in the BESEP and IDSEP.

2.6.2 Exterior Physical Security. External security requirements in most cases depend on the internal security measures provided in the facility design and on the type of protection required. Normally, external considerations, including building location and orientation and the use of protective barriers and lighting, are developed as part of the facility's security plan and specified in the BESEP. Defense Intelligence Agency DIAM 50-3, Physical Security Standards for Construction of Sensitive Compartmented Information Facilities, MIL-HDBK-1013/1, Design Guidelines for Physical Security of Fixed Land-Based Facilities, and MIL-HDBK-1013/10, Design Guidelines for Security Fencing, Gates, Barriers, and Guard Facilities, should be the primary criteria sources for design of the required facilities.

2.6.2.1 Perimeter Fencing. Use chain-link fencing for permanent areas. Use general-purpose barbed tape obstacle for temporary installations or where the terrain does not allow construction of chain-link fencing. Dual perimeter barriers are described in DIAM 50-3. Ensure the type of fencing selected does not interfere with any radiated signal of the facility. Alternative fence configurations are discussed in MIL-HDBK-1013/1. The following requirements are the minimum for normal protection:

a) Unless otherwise specified, locate the perimeter security fence at least 30 feet from enclosed structures (except guard shelters). Provide a clear zone not less than 20 feet wide immediately outside the fence. Keep this area devoid of buildings, parking areas, poles, guy line anchors, shrubs, trees, sign boards, and any other object that could conceal personnel. Grass is permissible, provided it is kept mowed. Provide a similar clear zone at least 30 feet wide immediately inside the fence. Ensure this area meets the requirements of the exterior clear zone, except for the installation of approved guard shelters and protective lighting poles.

b) Unless otherwise specified, provide barriers consisting of sensorized fencing with 3/4-inch vehicle restraining cable attached to the fence.

c) Ensure chain-link fencing conforms to Federal Specification RR-F-191, Wire Fencing (Chain-Link Fabric). Provide a fence with a total height of 8 feet; 7-foot-high fence fabric plus top guard. Provide 9 gauge fabric with openings not greater than 2 inches. Provide a 45-degree outrigger maximum 18 inches long. Attach three evenly spaced strands of 12 gauge barbed wire to the outriggers. Ground fence fabric and barbed wire strands.

MIL-HDBK-1024/1

d) Protect utility openings, covers, sewers, culverts, tunnels, and other subsurface routes which penetrate the fence line in accordance with MIL-HDBK-1013/1 and MIL-HDBK-1013/10.

e) Keep the number of gates and perimeter entrances to the minimum required for safe and efficient operation.

f) Provide guard shelters when required by the IDSEP.

2.6.2.2 Security Lighting. Install lighting inside the perimeter security fence in a manner to illuminate the fence completely and to prevent an intruder from using the light poles and guy wires to gain access to the area. Provide illumination in accordance with the lighting requirements of MIL-HDBK-1013/1 and the following:

a) Illuminate areas shadowed by structures.

b) Ensure that failure of one lamp in a circuit will not affect other lamps in the same circuit.

c) Provide overlapping light distribution to minimize reductions in illumination levels upon lamp failure.

d) Protect components of the system from vandalism.

e) Provide lights on buildings.

f) Provide an emergency power generator within the security area. Provide emergency power source adequate to sustain protective lighting of critical areas and structures for 8 hours. Provide generator- or battery-powered lights at key control points in case a failure disables the secondary power supply.

g) Install special-purpose lighting (such as fog penetration) when climatic or other local factors dictate.

h) Provide additional lighting for (CCTV) security surveillance, as necessary.

2.6.2.3 Intrusion Detection Systems (IDS). Provide IDS when required by the level of security assigned to the facility. Refer to NAVFAC DM-13.02, Commercial Intrusion Detection Systems (IDS). The IDSEP or user command shall provide specific IDS requirements.

2.6.2.4 Closed Circuit Television (CCTV). Provide CCTV when required to supplement security guard personnel, assist in threat assessment and surveillance. Refer to MIL-HDBK-1013/1.

## MIL-HDBK-1024/1

### 2.6.3 Interior Physical Security

2.6.3.1 Delay Times. Guidelines for selecting and designing facility components to meet specified delay times are provided in MIL-HDBK-1013/1. Procedures for determining delay times, if not specified by the IDSEP or the user command, are given in MIL-HDBK-1013/1.

2.6.3.2 Building Layout. Portions of the building requiring special security consideration will be identified by the IDSEP or by the user command.

2.6.3.3 Wall Construction. Design secure area wall using 4 inches of reinforced concrete or 8 inches of solid masonry, without windows, and with controlled access. Refer to DIAM 50-3 and MIL-HDBK-1013/1.

2.6.3.4 Roof and Floor Construction. Provide at least 4 inches of reinforced concrete for roof and floor construction. Hardening methods for other types of construction are provided in MIL-HDBK-1013/1. False ceilings or raised floors provide a means of concealment. False ceilings or floors are considered part of the protected area to which they are attached; therefore, ensure the true walls, floors, and ceilings meet the applicable requirements. Provide at least one quick-remove access panel, 18 by 18 inches, for each 400 square feet of false ceiling or floor area.

2.6.3.5 Exterior Doors. Provide entry and exit doors of secure areas as specified in the IDSEP or DIAM 50-3. Provide exterior doors with delay times commensurate with those of the structure in which they are installed.

2.6.3.6 Windows, Air Vents, and Ducts. Windows, ducts, and other openings that breach the facility perimeter require protection as specified in DIAM 50-3 and MIL-HDBK-1013/1. Openings which exceed the man passable size of 96 square inches require protection.

2.6.3.7 Roof Doors and Hatches. Secure roof doors and hatches with internal padlocks and hasps meeting the provisions of MIL-P-43607, Padlock, Key Operated, High Security, Shrouded Shackle. Alternatively, provide roof doors with a cylindrical case or bored lockset. Mount such locksets, when installed, with the lock cylinder to the exterior.

2.6.3.8 Cipher Locks. If required for control of routine access, install an electrically controlled and operated latch mechanism for interior doors. Ensure radio frequency (RF) emissions meet the requirements of Military Standard MIL-STD-461, Electromagnetic Emission and Susceptibility Requirements for the Control of Electromagnetic Interference, for Class II-A equipment. Ensure mechanisms do not mate or interface with other locksets. Add separate surface-mounted night latches or specialty hardware to the door to accommodate the electrically operated mechanism. Do not use key-operated bypass cylinders.

MIL-HDBK-1024/1

2.6.4 Vaults. Vaults or vault construction will be specified by the IDSEP or the user command. Specific criteria for construction and installation are given in DIAM 50-3 and MIL-HDBK 1013/1.

2.6.4.1 Safety and Emergency Devices. Equip vault doors with an emergency escape device and the following:

- a) Illuminated light switch.
- b) Emergency light (if the vault is otherwise unlighted).
- c) Interior alarm switch or other device (such as a telephone) to permit a person in the vault to communicate with a vault custodian, guard, or guard post.
- d) Instructions on obtaining release permanently affixed to the inside of the door or prominently displayed elsewhere inside the vault.
- e) Bank vault ventilator approved by Underwriters Laboratories, Inc. (UL), if the vault is not otherwise served by forced air ventilation.

2.6.4.2 Fire Protection. Equip the vault with at least one portable, hand-held, carbon dioxide fire extinguisher UL approved.

## 2.7 Safety and Health

2.7.1 General Requirements. Design occupied buildings with maximum consideration given to safety and health. Refer to Title 29, CFR, Part 1910, Occupational Safety and Health Standards, with particular emphasis on noise control for hearing conservation and safety standards for toxic and hazardous substances. Provide suitable facilities for quick drenching or flushing of the eyes and body within the work area for immediate emergency use where any person may be exposed to injurious corrosive materials.

2.7.2 Human Engineering. Consider safety in relation to operational function, accessibility for maintenance and repair, physical layout for traffic, interface with other equipment, and environmental factors, such as lighting, temperature, and humidity. Refer to MIL-STD-882, System Safety Program Requirements, and MIL-STD-1472, Human Engineering Design Criteria for Military Systems, Equipment, and Facilities.

2.7.3 Electromagnetic Hazards. Many facilities discussed herein contain equipment that radiates an electromagnetic signal. Consider the effect of electromagnetic radiation (EMR) on personnel (HERP), ordnance (HERO), and fuel (HERF) when planning and designing facilities housing EMR emitting equipment. Provide safety measures to eliminate or reduce hazardous conditions. Refer to MIL-HDBK-1012/1.

MIL-HDBK-1024/1

2.7.4 Fire Protection. Refer to MIL-HDBK-1008 and NFPA 232, Protection of Records for design criteria and guidance. Use MIL-HDBK-1008 as a minimum standard to determine types of fire protection required as well as specific criteria to use.

2.7.4.1 Classifications. MIL-HDBK-1008 provides guidance for classification of occupancy and occupancy hazard classification. Classification of occupancy is a function of the intended use of the building and is one of seven major occupancy classification groups. Occupancy hazard classification is a function of the quantity and combustibility of the contents. The principal hazard classifications are light, ordinary, and extra.

2.7.4.2 Windowless Buildings. A number of facilities, or portions of facilities, discussed herein may be classified as windowless buildings. Provide additional fire protection and life safety measures for windowless buildings in accordance with MIL-HDBK-1008 and NFPA 101.

2.7.5 Life Safety. Provide life safety systems in accordance with NFPA 101 and MIL-HDBK-1008.

2.8 Design Standards. The information and references herein are presented as a guide for the designer. It is intended that the requirements presented herein be considered a minimum and that they take precedence over requirements of the references or from other sources. However, if in the best judgement of the designer, a more restrictive requirement is appropriate, the more restrictive requirement may be applied after consulting with the user.

## MIL-HDBK-1024/1

## Section 3: AIR NAVIGATION AIDS/AIRCRAFT LANDING SYSTEMS

3.1 Air Navigation Aids

3.1.1 Function. Air navigation aid facilities are for fixed ground station electronic equipment which transmits bearing, identification, and distance information to properly equipped aircraft. Air navigation aid facilities consist of the following:

3.1.1.1 Very High Frequency (VHF) Omni-Directional Range (VOR). The VOR facility is a VHF, fixed ground-based station which continuously transmits bearing, identification, and with proper equipment, distance information to properly equipped aircraft. See Facility Plate 133-25 (Sheets 1 through 4 of 4).

3.1.1.2 Tactical Air Navigation (TACAN). The TACAN facility is an ultra high frequency (UHF) ground-based station which continuously transmits bearing, identification, and distance information to properly equipped aircraft when interrogated. See Facility Plate 133-25 (Sheets 1 through 4 of 4).

3.1.1.3 Very High Frequency (VHF) Omni-Directional Range/Tactical Air Navigation (VORTAC). The VORTAC facility is a VHF/UHF fixed ground-based station which continuously transmits bearing, identification, and distance information to properly equipped aircraft when distance measuring equipment (DME) is installed. See Facility Plate 133-25 (Sheets 1 through 4 of 4).


3.1.2 Location. Locate the air navigation aid facility, if possible, in an area adjacent to the intersection of the primary runways. Locate the facility a minimum of 750 feet from the centerline of runways, and a minimum of 250 feet from centerline taxiways. When the facility is located off the airfield, consider selecting a site with one or more flight path courses providing an approach to the primary runway. Refer to FAA AC 150/5300-13, Airport Design, and FAA Order 6820.10, VOR, VOR/DME, and VORTAC Siting Criteria.

3.1.3 Architectural and Structural Requirements. Provide the following:


- a) Adequate space for equipment and equipment maintenance.
- b) Clear ceiling height of 10 feet.
- c) Work bench.
- d) Restroom (refer to par. 2.4.8).

3.1.3.1 Structure. Provide sufficient roof area to accommodate VOR and VORTAC roof mounted antenna counterpoise. Consider an extended roof overhang or an antenna tower to accommodate a large antenna counterpoise.


MIL-HDBK-1024/1



MIL-HDBK-1024/1




MIL-HDBK-1024/1







MIL-HDBK-1024/1



MIL-HDBK-1024/1


Any Facility located within the Airfield Safety Clearance Zone as defined by NAVFAC P 80.3 requires a criteria waiver approved by COMNAVAIRSYSCOM (Code 09Y1). Any equipment that must be located in violation of the Safety Clearance Zone criteria shall be coordinated with the In Service Engineering Agent (ISEA). The ISEA must ensure that such equipment will be sited as far as possible away from the operating surface toward the outer limits of the NAVFAC P80.3 criteria.



TITLE	DATE	FACILITY PLATE	SHEET
TACAN Building Layout	11/92	133-25	2 Of 4

MIL-HDBK-1024/1


Any Facility located within the Airfield Safety Clearance Zone as defined by NAVFAC P 80.3 requires a criteria waiver approved by COMNAVAIRSYSCOM (Code 09Y1). Any equipment that must be located in violation of the Safety Clearance Zone criteria shall be coordinated with the In Service Engineering Agent (ISEA). The ISEA must ensure that such equipment will be sited as far as possible away from the operating surface toward the outer limits of the NAVFAC P80.3 criteria.



TITLE	DATE	FACILITY PLATE	SHEET
TACAN Building Section	11/92	133-25	3 Of 4




MIL-HDBK-1024/1




<p>TITLE VORTAC Facility Site Plan</p>	<p>DATE 11/92</p>	<p>FACILITY PLATE 133-25</p>	<p>SHEET 1 Of 4</p>
--	-----------------------	----------------------------------	-------------------------

MIL-HDBK-1024/1

Any Facility located within the Airfield Safety Clearance Zone as defined by NAVFAC P 80.3 requires a criteria waiver approved by COMNAVAIRSYSCOM (Code 09Y1). Any equipment that must be located in violation of the Safety Clearance Zone criteria shall be coordinated with the In Service Engineering Agent (ISEA). The ISEA must ensure that such equipment will be sited as far as possible away from the operating surface toward the outer limits of the NAVFAC P80.3 criteria.




Graphic Scale in Feet



TITLE	DATE	FACILITY PLATE	SHEET
VORTAC Building Layout	11/92	133-25	2 Of 4

MIL-HDBK-1024/1





MIL-HDBK-1024/1

3.1.3.2 Windows. Do not provide windows.

3.1.3.3 Premanufactured Building. Consider the use of a premanufactured building as described in par. 2.3.12.

3.1.4 Electrical Requirements. To avoid potential interference with radar transmissions locate power, communications, and control cables underground within 1,000 feet from the facility. Ensure electrical systems do not interfere with radar transmissions.

3.1.4.1 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described in par. 2.5.7. Provide emergency power to the entire facility.

3.1.5 Security. VOR, TACAN, and VORTAC facilities are normally located within the airfield restricted area. This siting typically meets the minimum security measures for external security. When the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6.

3.1.6 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

## 3.2 Aircraft Landing Systems

### 3.2.1 Microwave Landing System (MLS)/Instrument Landing System (ILS)


3.2.1.1 Function. The MLS and ILS buildings are facilities that contain electronic equipment used in precision instrument approaches.

3.2.1.2 Microwave Landing System (MLS). The MLS provides azimuth, distance, elevation, and guide path position to aircraft on a precision approach to the MLS instrumented runway. The MLS operates in a narrow band microwave frequency. See Facility Plate 134-40 (Sheets 1 through 4 of 4).


3.2.1.3 Instrument Landing System (ILS). The ILS provides azimuth, distance, elevation, and glide path position to aircraft on a precision approach to the ILS instrumented runway. The ILS operates in the VHF and UHF radio bands. See Facility Plate 134-40 (Sheets 1 through 6 of 6).

3.2.1.4 Location - MLS Transmitters. Locate azimuth transmitter on the extended runway centerline, 700 to 1,200 feet from the end of runway. Locate elevation transmitter 600 to 900 feet set back from runway approach threshold, offset 250 to 600 feet from runway centerline on the runway side opposite of taxiways.


MIL-HDBK-1024/1



MIL-HDBK-1024/1




MIL-HDBK-1024/1






MIL-HDBK-1024/1




Not to Scale

TITLE ILS Facility: Marker Siting	DATE 11/92	FACILITY PLATE 134-40	SHEET 1 Of 6
--------------------------------------	---------------	--------------------------	-----------------


MIL-HDBK-1024/1




MIL-HDBK-1024/1



MIL-HDBK-1024/1



MIL-HDBK-1024/1





MIL-HDBK-1024/1

3.2.1.5 Location - ILS Transmitters. Provide separate facilities for glide slope antenna transmitter equipment, for localizer antenna transmitter equipment and for marker antenna equipment. Refer to FAA Order 6750.16, Siting Criteria for Instrument Landing Systems and FAA AC 150/5300-13.

3.2.1.6 Structure. MLS and ILS transmitter equipment is provided in a self-contained structure by the system supplier. Provide concrete foundations to mount equipment structures. Ensure MLS and ILS structures are frangible. Refer to FAA ER-530-81-04.

3.2.1.7 Mechanical. No mechanical systems are required.

3.2.1.8 Electrical. Provide underground power, communications, and control cables, beginning at a point 1,000 feet outside of the MLS and ILS facilities. Locate electrical equipment which is not frangible, such as transformers, outside the runway clear zone or primary surface. Ensure electrical systems do not interfere with radio transmissions.

3.2.1.9 Emergency Electrical Power. MLS and ILS equipment is supplied with backup battery power. No emergency generator is required.

3.2.1.10 Lighting. No site lighting is required. Obstruction lighting is provided with the equipment.

3.2.1.11 Site Work. Design site work to meet the criteria in FAA Order 6750.16 and par. 2.2.

3.2.1.12 Security. MLS and ILS facilities are normally located within the airfield restricted area which would typically meet the minimum security measures for external security. If the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area, additional measures will be required to meet the minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6.

3.2.1.13 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

3.2.2 Precision Approach Landing System (PALS)/Precision Approach Radar (PAR)

3.2.2.1 Function. The PALS and PAR buildings house radar systems used to guide aircraft on final approach.

MIL-HDBK-1024/1

3.2.2.2 Precision Approach Landing System (PALS). The PALS is an unattended, self-contained radar system. The PALS detects azimuth, elevation, and range information of aircraft on final approach to PALS instrumented runways. This information is displayed in the Military Terminal Radar Approach Control Facility (MTRACON). See Facility Plate 134-40 (Sheets 1 through 4 of 4).

3.2.2.3 Precision Approach Radar (PAR). The PAR is an unattended self-contained radar system. The PAR detects azimuth, elevation, and range information of aircraft on final landing approach to PAR instrumented runways. This information is displayed in the MTRACON. The PAR can be mounted on a fixed base or on a turntable. See Facility Plate 134-40 (Sheets 1 through 8 of 8).

3.2.2.4 Location. Locate PALS and PAR sites adjacent to the instrumented runway or runway intersection. Refer to NAVEXLEX 0101,107; Naval Shore Electronics Criteria.

3.2.2.5 Structure. The PALS and PAR systems are housed in a transportable shelter provided by the system manufacturer. Provide the following:

- a) Reinforced concrete foundations for PALS antenna tower.
- b) Reinforced concrete platform for the fixed mounted PAR.
- c) Reinforced concrete foundations to support the turntable mounted PAR frame. Provide concrete anchor blocks for turntable stop anchors bolts.

3.2.2.6 Mechanical Requirements. No mechanical systems are required.


3.2.2.7 Electrical Requirements. Provide underground power, communications, and control cables at a point 1,000 feet from the radar set. Ensure electrical systems do not interfere with radio and radar transmissions.

3.2.2.8 Emergency Electrical Power. Provide an emergency generator system as described in par. 2.5.7. Provide emergency power to the entire facility.


3.2.2.9 Lighting. No site lighting is required. Obstruction lighting is provided with the equipment.

3.2.2.10 Paved Equipment Areas. Design paved equipment areas for the maximum anticipated vehicle wheel load. Consider concrete pedestals to distribute concentrated loads from equipment supports. Refer to NAVFAC DM-5.04.


MIL-HDBK-1024/1



MIL-HDBK-1024/1




MIL-HDBK-1024/1






MIL-HDBK-1024/1




MIL-HDBK-1024/1




TITLE PAR Facility Site Plan	DATE 11/92	FACILITY PLATE 134-40	SHEET 2 Of 8
---------------------------------	---------------	--------------------------	-----------------

MIL-HDBK-1024/1



MIL-HDBK-1024/1




TITLE PAR Facility:  
Turntable Mounted Radar Elevation

DATE 11/92


FACILITY PLATE 134-40

SHEET 4 Of 8

MIL-HDBK-1024/1




Note: Orientation of Radar Equipment to be in Accordance with BESEP.




TITLE PAR Facility: Fixed Mounted Radar Plan	DATE 11/92	FACILITY PLATE 134-40	SHEET 5 Of 8
--	---------------	--------------------------	-----------------

MIL-HDBK-1024/1



MIL-HDBK-1024/1





MIL-HDBK-1024/1

3.2.2.11 Security. PALS and PAR facilities are normally located within the airfield restricted area which typically meet the minimum security measures for external security. When the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6.

3.2.2.12 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

MIL-HDBK-1024/1

## Section 4: AIR SURVEILLANCE RADAR SYSTEMS

4.1 Function. Air surveillance radar facility buildings provide housing for electronic radar equipment used to detect and display location information about in-flight aircraft. These facilities are unattended.

4.2 Radar Systems. This section describes the facilities which support the radar systems discussed in pars. 4.2.1 and 4.2.2.

4.2.1 Airport Surveillance Radar (ASR). The ASR is an electronic radar system used to obtain the range and azimuth of an aircraft. When equipped with an ATCRBS, the ASR obtains altitude and identification of the aircraft. Information obtained by the ASR and ATCRBS is displayed in the MTRACON, the air traffic control tower with ground controlled approach or a joint control facility (JCF). The ASR is used to control aircraft on overflight, approach, and departure flight paths at a terminal facility. See Facility Plate 133-75 (Sheets 1 through 3 of 3).

4.2.2 Air Route Surveillance Radar (ARSR). The ARSR is an electronic radar system used to obtain the range and azimuth of an aircraft. When equipped with an ATCRBS, the ARSR obtains altitude and identification of the aircraft. Information is displayed in the FACSFAC or JCF. The ARSR is used to control airspace and enroute aircraft beyond the limits of an ASR. See Facility Plate 133-76 (Sheets 1 through 3 of 3).

4.3 Location. Locate the ASR and ARSR building adjacent to the radar facility antenna tower. Locate the ASR facility no less than one-half mile from the closest runway to be served. The ASR facility at Range Airspace Surveillance Sites (RASS) may be located further away. Locate the facility to minimize obstruction to radar transmissions. Refer to NAVELEX 0101,107; FAA Order 6310.6, Primary/Secondary Terminal Radar Siting Handbook; and FAA Order 6340.15, Primary/Secondary En Route Radar Siting Handbook.


4.4 Architectural and Structural Requirements. Provide the following:

- a) Adequate space for equipment and equipment maintenance.
- b) Clear ceiling height of 10 feet.
- c) Work bench.
- d) Restroom (refer to par. 2.4.8).

4.4.1 Structure. Design roof structural system to support cable trays and radar equipment wave guides.


4.4.2 Floors. Provide vinyl tile flooring in equipment room. Refer to par. 2.3.8.2.

MIL-HDBK-1024/1




NOTE

Location of building and tower on site is dependent on equipment type and site conditions.  
 Coordinate location of transformer and generator fuel tank with type of generator enclosure.




TITLE ASR Facility Site Plan	DATE 11/92	FACILITY PLATE 133-75	SHEET 1 Of 3
---------------------------------	---------------	--------------------------	-----------------

MIL-HDBK-1024/1






MIL-HDBK-1024/1




**NOTE**

Location of building and tower on site is dependent on equipment type and site conditions.  
 Coordinate location of transformer and generator fuel tank with type of generator enclosure.



TITLE ARSR Facility Site Plan	DATE 11/92	FACILITY PLATE 133-76	SHEET 1 Of 3
----------------------------------	---------------	--------------------------	-----------------

MIL-HDBK-1024/1



<p>TITLE ARSR Building Layout</p>	<p>DATE 11/92</p>	<p>FACILITY PLATE 133-76</p>	<p>SHEET 2 Of 3</p>
---------------------------------------	-----------------------	----------------------------------	-------------------------



## MIL-HDBK-1024/1

- 4.4.3 Ceilings. Provide acoustical tile ceilings. Refer to par. 2.3.8.9.
- 4.4.4 Windows. Do not provide windows.
- 4.5 Mechanical Requirements. Design mechanical systems to meet the criteria in pars. 2.4, 4.5.1, and 4.5.2. Ensure mechanical systems do not interfere with radar transmissions.
- 4.5.1 Heating. Provide a minimum temperature of 70 degrees F.
- 4.5.2 Air Conditioning. Provide two separate air conditioning systems, each capable of handling the entire load independently. One unit will function as a secondary backup unit should the primary unit fail. Provide the following:
- a) Separate thermostat controls for each unit.
  - b) Interlocked primary and secondary units to prevent simultaneous operation.
- 4.6 Electrical Requirements. To avoid potential interference with radar transmissions locate power, communications, and control cables underground within 1,500 feet from the antenna site. Ensure electrical systems do not interfere with radar transmissions.
- 4.6.1 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described in par. 2.5.7. Provide emergency power to the entire radar facility.
- 4.6.2 Uninterrupted Power Supply (UPS). Provide non-redundant UPS in accordance with par. 2.5.8. Use the anticipated load to determine the size of the UPS.
- 4.7 Security. Air surveillance radar facilities are normally located within restricted areas which would typically meet the minimum security measures for external security. When the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6.
- 4.8 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

MIL-HDBK-1024/1

## Section 5: COMMUNICATIONS FACILITIES

5.1 Function. Communications facilities contains remote electronic communications and linking equipment used for ground-to-air communications with tactical and transient aircraft, to control aircraft departures and arrivals, and for communications with other agencies involved in air traffic control or aviation support. Communications facilities consist of the following buildings:

5.1.1 Radio Receiver Building. The receiver building contains receiver and repeater equipment, antenna coupling equipment, and maintenance and test equipment. See Facility Plate 131-35 (Sheets 1 through 3 of 3).

5.1.2 Radio Transmitter Building. The transmitter building contains transmitting equipment, antenna coupling equipment, and maintenance and test equipment. See Facility Plate 131-50 (Sheets 1 through 3 of 3).

5.1.3 Collocated Radio Transmitter and Receiver Building. The collocated transmitter and receiver building contains transmitting equipment, antenna coupling equipment, receiver and repeater equipment, and maintenance and test equipment. See Facility Plate 131-35/50 (Sheets 1 through 3 of 3).

5.1.4 Remote Data Link Building. The remote data link building provides housing for a suite of communications linking equipment. Equipment suites typically include satellite communications, radio, and television microwave. See Facility Plate 131-20 (Sheets 1 through 3 of 3).

5.2 Location. Locate radio communications buildings in antenna field to provide minimum length of cable from antenna to radio communications equipment. Refer to the BESEP and consider planned expansion of airfield systems when locating communications facilities. Refer to NAVELEX 0101, 107 and FAA Order 6580.2, Remote Communications Facility Siting Criteria Handbook.


5.3 Architectural and Structural Requirements. Provide the following:

- a) Adequate space for equipment and equipment maintenance.
- b) Clear ceiling height of 10 feet.
- c) Work bench.
- d) Restroom (refer to par. 2.4.8).
- e) Floor trenches with covers or suspended cable trays.


5.3.1 Structure. Design roof framing system to support roof-mounted antennas and suspended cable trays, when required.

5.3.2 Windows. Do not provide windows.


MIL-HDBK-1024/1



MIL-HDBK-1024/1




Any Facility located within the Airfield Safety Clearance Zone as defined by NAVFAC P 80.3 requires a criteria waiver approved by COMNAVAIRSYSCOM (Code 09Y1). Any equipment that must be located in violation of the Safety Clearance Zone criteria shall be coordinated with the In Service Engineering Agent (ISEA). The ISEA must ensure that such equipment will be sited as far as possible away from the outer limits of the NAVFAC P80.3 criteria.




TITLE	DATE	FACILITY PLATE	SHEET
Radio Receiver Building Layout	11/92	131-36	2 Of 3



MIL-HDBK-1024/1




MIL-HDBK-1024/1






MIL-HDBK-1024/1



MIL-HDBK-1024/1

Any Facility located within the Airfield Safety Clearance Zone as defined by NAVFAC P 80.3 requires a criteria waiver approved by COMNAVAIRSYSCOM (Code 09Y1). Any equipment that must be located in violation of the Safety Clearance Zone criteria shall be coordinated with the In Service Engineering Agent (ISEA). The ISEA must ensure that such equipment will be sited as far as possible away from the operating surface toward the outer limits of the NAVFAC P80.3 criteria.



<b>TITLE</b> Collocated Radio Transmitter And Receiver Building Layout	<b>DATE</b> 11/92	<b>FACILITY PLATE</b> 131-35/50	<b>SHEET</b> 2 Of 3
---	----------------------	------------------------------------	------------------------


MIL-HDBK-1024/1

```


+)))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))
*
*                                     Collocated Transmitter *
*                                     and Receiver *
*
* Plumbing Requirements (G.P.M.): *
*   Water; *
*     Cold 8 *
*
*   Fire Protection Requirements *
*     Not Included *
*
* Heating Requirements (BTU/HR x 1000): *
*   (Inside Design Temperature = 40 Degs. F) *
*   Outside Design Temperature -5 Degs. F 36 *
*                               +5 Degs. F 28 *
*                               +15 Degs. F 20 *
*                               +25 Degs. F 12 *
*
* Air Conditioning Requirements (BTU/HR x 1000): *
*   Based on 91 Degs. D.B. 76 Degs. W.B. Outside Design *
*   Conditions; Cooling Load 147 *
*
*   Heat rejected to conditioned spaces by energized test. *
*   Equipment & parts under repair not included. *
*
* Electrical Requirements (KVA): *
*   Lights; *
*     Connected Load 4.0 *
*     Estimated Demand 2.6 *
*
*   Power; *
*     Connected Load 41.0 *
*     Estimated Demand 26.7 *
*
*   Air Conditioning; *
*     Connected Load 54.0 *
*     Estimated Demand 35.1 *
*
*   Total; *
*     Connected Load 99.0 *
*     Estimated Demand 64.4 *
*     Emergency Generator (KW) 50.0 *
*
* Areas (SF): *
*   Gross area including mechanical *
*   equipment room 1,408 *
*
* General Notes: *
*   Plumbing cold water is for restrooms, *
*   when required. *
/))))))))))))))))))))))))))))))))))0))))0))))))))))))))))))0))))))1
* TITLE * DATE * FACILITY PLATE * SHEET *
* Collocated Radio Transmitter And * 7/92 * 131-35/50 * 3 OF 3 *
* Receiver Facility Design Notes * * * *
.)))))))))))))))))))))))))))))))))))2))))2))))))))))))))))))2))))))-

```

MIL-HDBK-1024/1



MIL-HDBK-1024/1



Any Facility located within the Airfield Safety Clearance Zone as defined by NAVFAC P 80.3 requires a criteria waiver approved by COMNAVAIRSYSCOM (Code 08Y1). Any equipment that must be located in violation of the Safety Clearance Zone criteria shall be coordinated with the In Service Engineering Agent (ISEA). The ISEA must ensure that such equipment will be sited as far as possible away from the operating surface toward the outer limits of the NAVFAC P80.3 criteria.



MIL-HDBK-1024/1

5.3.3 Premanufactured Buildings. Consider using a premanufactured building as described in par. 2.3.12.

5.4 Electrical Requirements. To avoid potential interference with radio communications, locate power, communications, and control cables underground within 1,000 feet of the antenna field. Ensure facility electrical systems do not interfere with radio communications.

5.4.1 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described in par. 2.5.7. Provide emergency power to the entire communications facility.

5.5 Security. Communications facilities are normally located within restricted areas which would typically meet the minimum security measures for external security. When the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6.

5.6 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

MIL-HDBK-1024/1

## Section 6: AIR TRAFFIC CONTROL FACILITIES

6.1 Military Terminal Radar Approach Control Facility (MTRACON)

6.1.1 Function. The MTRACON building contains equipment used for controlling air traffic and is staffed by air traffic controllers and air operations, administrative, and maintenance support personnel. The ASR, PAR, PALS, transmitting and receiving sites, and navigation aids (NAVAIDS), which are remotely located, are monitored and controlled in the MTRACON. The MTRACON contains an IFR control room which includes the radar display consoles and communications control equipment. An adjacent terminal equipment room houses automation central (or terminal) equipment, maintenance positions and audio/video tape recorders. An office for the FAA liaison officer is required at joint operated Navy/FAA terminal radar approach control facilities.

6.1.2 Location. Locate the MTRACON building adjacent to the air traffic control tower and aircraft operations building where siting requirements permit.

6.1.3 Architectural and Structural Requirements. See Facility Plate 133-72 (Sheets 1 through 3 of 3). Provide the following:

a) Removable, modular, access flooring in the IFR and terminal equipment rooms with 18 inches of clearance provided between the floor panels and subfloor to accommodate wiring and insulated piping. See par. 2.3.5.2.

b) A 9-foot clear ceiling height above accessible flooring.

c) Built-in workbenches and shelving in the terminal equipment room.

d) Facility and restroom areas readily accessible by the physically handicapped.


e) Interior and exterior acoustical treatment to attain the room criteria described in par. 2.3.1. Soft textured acoustical wall panels in the IFR control room.

f) Cable troughs or conduits between the air traffic control tower and the MTRACON for intrafacility cabling. The exact dimensions of the cable trough or size and number of conduits are specified in the BESEP.


6.1.3.1 Windows. Do not provide windows in IFR or terminal equipment rooms. Provide insulated glazing for noise reduction in administrative areas. Refer to par. 2.3.10.

6.1.4 Electrical Requirements

MIL-HDBK-1024/1



MIL-HDBK-1024/1





MIL-HDBK-1024/1

6.1.4.1 Uninterrupted Power Supply (UPS). Provide non-redundant UPS in accordance with par. 2.5.8. Use the anticipated load to determine the size of the UPS.

6.1.4.2 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described in par. 2.5.7. Provide emergency power to the following:

- a) Loads as required by NFPA-101.
- b) Electronic equipment in the IFR and terminal equipment rooms.
- c) Mechanical systems supporting electronic equipment.
- d) Exterior security lighting and security systems.

6.1.4.3 400-Hz Power. Provide 400-Hz power in accordance with par. 2.5.9 when required by the BESEP.

6.1.5 Lighting. Design lighting in accordance with par. 2.5.6. Provide dimmer adjustable red lights in the IFR room.

6.1.6 Security. The MTRACON is normally located within restricted areas which typically meet the minimum security measures for external security. If the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. Security at the main building entrance usually requires a single entry point with visitor control. Remote locks, video cameras, card readers, and/or key pads may be required by COMNISCOM as components of the IDS. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6. Provide the following:

- a) Electronic cipher door locks at interior entrance doors to IFR and terminal equipment rooms.
- b) Exterior doors in emergency generator/electrical and terminal equipment rooms with no access hardware on the outside.

6.1.7 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

## 6.2 Fleet Area Control and Surveillance Facility (FACSFAC)

6.2.1 Function. The FACSFAC building houses the Navy Tactical Data System/Advanced Combat Direction System (NTDS/ACDS) equipment and personnel to provide a variety of services to air, surface, and subsurface units. These services are provided to both military and civilian users and include radar

MIL-HDBK-1024/1

surveillance and various forms of air traffic control in warning and other special airspace areas. Other services include surface operating area management, ground controlled intercept, operating area scheduling, and range control. The FACSFAC normally operates continuously.

6.2.2 Location. Locate the FACSFAC building as a stand-alone facility.

6.2.3 Architectural and Structural Requirements. See Facility Plate 133-73 (Sheets 1 through 3 of 3). Provide the following:

a) Removable, modular, access flooring in the operations, NTDS/ACDS system, and the equipment/maintenance rooms with 18 inches of clearance provided between the floor panels and subfloor to accommodate wiring and insulated piping. Refer to par. 2.3.5.2.

b) Interior and exterior acoustical treatment to attain the room criteria described in par. 2.3.1. Soft textured acoustical wall panels and movable sound absorbent partitions in the operations room.

c) A clear ceiling height of 14 feet (finished floor to ceiling) in the operations area.

d) A tiered seating area in projection auditorium.

e) RF shielding throughout the crypto room. Refer to MIL-HDBK-1195, Radio Frequency Shielded Enclosures and NAVFAC Instruction 11010.44. Shielding requirements shall be confirmed by Naval Electronics Systems Security Engineering Center (NESSEC).

f) Facility and restroom areas readily accessible by the physically handicapped.

6.2.3.1 Windows. Do not provide windows in operations, NTDS/ACDS system, and equipment/maintenance rooms. Provide insulated glazing for noise reduction in administrative areas. Refer to par. 2.3.10.

6.2.4 Mechanical Requirements. Design the mechanical system to meet the criteria in pars. 2.4, 6.2.4.1, and 6.2.4.2. Provide the following:


a) Automatic thermostatic control.

b) A four-pipe chilled/hot water distribution system with separate air handlers for each zone or dehumidifying system to work in conjunction with the air conditioning system.

c) Capability for future expansion of the HVAC system. Use piping designed for low friction and velocity losses at the maximum flows expected.

d) Chilled water for NTDS/ACDS system in accordance with BESEP.

MIL-HDBK-1024/1




Any Facility located within the Airfield Safety Clearance Zone as defined by NAVFAC P 80.3 requires a criteria waiver approved by COMNAVAIRSYSCOM (Code 09Y1). Any equipment that must be located in violation of the Safety Clearance Zone criteria shall be coordinated with the In Service Engineering Agent(ISEA).

Graphic Scale in Feet  
0 25 50 75 100

TITLE	DATE	FACILITY PLATE	SHEET
FACSFAC Facility Site Plan	11/92	133-73	1 Of 3

MIL-HDBK-1024/1



MIL-HDBK-1024/1

```
+))))))))))))) ,
*
*                      F A C S F A C
*
* Plumbing Requirements (GPM):
* Water;
*
* Cold 56
* Hot
* Recovery Rate (100 Degs. Rise) 75
* Storage Gal 160
* Fire Protection Requirements
* Not Included
*
* Heating Requirements (BTU/HR x 1000):
* (Inside Design Temperature = 72 Degs. F)
* Outside Design Temperature -5 Degs. F 380
* +5 Degs. F 330
* +15 Degs. F 300
* +25 Degs. F 230
*
* Air Conditioning Requirements (BTU/HR x 1000):
* Based on 91 Degs. D.B. 76 Degs. W.B. Outside Design
* Conditions; Cooling Load 1095
*
* Heat rejected to conditioned spaces by energized test.
* Equipment & parts under repair not included.
*
* Electrical Requirements (KVA):
* Lights;
* Connected Load 90
* Estimated Demand 63
*
* Power;
* Connected Load 418
* Estimated Demand 293
*
* Air Conditioning;
* Connected Load 377
* Estimated Demand 264
*
* Total;
* Connected Load 885
* Estimated Demand 620
* Emergency Generator (KW) 400
*
* Areas (SF):
* Gross area including mechanical
* equipment room 27,650
*
* General Notes:
*
*)))))))))))))) 0)))))) 0)))))) 0)))))) 1
* TITLE * DATE * FACILITY PLATE * SHEET *
* F A C S F A C Facility Design Notes * 11/92 * 133-73 * 3 OF 3 *
.)))))))))))))) 2)))))) 2)))))) 2)))))) -
```

## MIL-HDBK-1024/1

## 6.2.4.1 Air Conditioning. Provide the following:

a) Two parallel piped air cooled chillers, each designed for 60 percent of the total building cooling load. Alternate operation of chillers automatically on a regular basis when load is less than 60 percent. Consider cold storage to minimize power peaks.

b) One chilled water circulation pump for each chiller plus a manifold spare pump. Design chiller circuitry so that the pump shall operate and water flow before the chiller is energized. The spare pump may be manually operated. Provide secondary chilled water loops with three-way valves at coils in each circuit to result in constant flow through chiller.

c) Divide the building into three cooling zones: administrative areas, operations areas, and the equipment areas. Provide separate air handlers and ducting systems for each zone. Provide sound attenuators for supply duct work. Consider more than one air handler for large zones.

d) Provide two air handlers for the operations, the NTDS/ACDS, and terminal distribution rooms. Design air handler controls to regulate the units as primary and secondary with each unit alternating as the primary. Provide air handlers capable of controlling humidity, equipped with electric heat, and specifically designed for computer room applications. Refer to MIL-HDBK-1012/1.

6.2.4.2 Heating. Provide fuel oil or gas operated boiler heating system designed to accommodate the largest heating load anticipated. Provide two circulation pumps, each designed for 100 percent of the total building heating load. Design the pump controls to regulate the pumps as primary and secondary with each pump alternating as the primary.

6.2.5 Electrical Requirements

6.2.5.1 Uninterrupted Power Supply (UPS). Provide non-redundant UPS in accordance with par. 2.5.8. Use anticipated load to determine the size of UPS.

6.2.5.2 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described in par. 2.5.7. Provide emergency power to the following:

- a) Loads as required by NFPA-101.
- b) Electronic equipment in operations, the NTDS/ACDS, and equipment rooms.
- c) Building mechanical systems supporting electronic equipment.
- d) Exterior security lighting and security systems.

MIL-HDBK-1024/1

6.2.5.3 400-Hz Power. Provide 400-Hz power for the NTDS/ACDS in accordance with par. 2.5.9.

6.2.6 Security. The FACSFAC is normally located within restricted areas which meet the minimum security measures for external security. When the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area. Provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. Security at the main entrance usually requires a single entry point with visitor control. Remote locks, video cameras, card readers, and/or key pads may be required by COMNISCOM as components of the IDS. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6. Provide the following:

- a) Electronic cipher door locks at access points to operations room.
- b) Exterior doors in the operations, the NTDS/ACDS, equipment/maintenance, and mechanical/electrical rooms with no access hardware on the outside.
- c) CCTV.
- d) Security fencing and guard post for facilities located outside the secure area of the Naval installation.
- e) Personnel identification, visitor check-in, and control system to control ingress and egress.

6.2.7 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

### 6.3 Joint Control Facility (JCF)

6.3.1 Function. The JCF is a high density (air traffic) facility which collocates approach control responsibilities for two or more air stations or a combination of an approach control facility and a FACSFAC or Range Operations Center (ROC) under one roof. The JCF normally operates continuously.

6.3.2 Location. Locate the JCF adjacent to the air operations building when siting criteria permits. An air traffic control tower may be sited with the JCF.

MIL-HDBK-1024/1

6.3.3 Architectural and Structural Requirements. See Facility Plate 133-74 (Sheets 1 through 7 of 7). Provide the following:

a) Removable, modular, access flooring in the operations, the NTDS/ACDS, and the equipment/maintenance rooms with 18 inches of clearance provided between the floor panels and subfloor to accommodate wiring and insulated piping. Refer to par. 2.3.5.2.

b) Interior and exterior acoustical treatment to attain the room criteria described in par. 2.3.1. Soft textured acoustical wall panels and movable sound absorbent partitioning in the operations room.

c) A clear ceiling height of 14 feet (finished floor to ceiling) in the operations area.

d) A tiered seating area in projection auditorium.

e) RF shielding throughout the crypto room. Refer to MIL-HDBK-1195 and NAVFAC Instruction 11010.44. Shielding requirements shall be confirmed by NESSEC.

f) Facility and restroom areas readily accessible by the physically handicapped.

g) Cable troughs or conduits between the air traffic control tower and the JCF for intrafacility cabling. The exact dimensions of the cable trough or size and number of conduits are specified in the BESEP.

6.3.3.1 Windows. Do not use windows in operations, NTDS/ACDS system, and equipment/maintenance rooms. Provide insulated glazing for noise reduction in administrative areas. Refer to par. 2.3.10.

6.3.4 Mechanical Requirements. Design the mechanical system to meet the criteria in pars. 2.4, 6.3.4.1, and 6.3.4.2. Provide the following:


a) Automatic thermostatic control.

b) A four-pipe chilled/hot water distribution system with separate air handlers for each zone or dehumidifying system to work in conjunction with the air conditioning system.

c) Capability for future expansion of the HVAC system. Use piping designed for low friction and velocity losses at the maximum flows expected.

d) Chilled water for the NTDS/ACDS in accordance with the BESEP.

MIL-HDBK-1024/1




PLAN

Graphic Scale in Feet  
 0 25 50 75 100


<p>TITLE                  Joint Control Facility (Medium Density)                  Site Plan</p>	<p>DATE                  11/92</p>	<p>FACILITY PLATE                  133-74</p>	<p>SHEET                  1 Of 7</p>
--	--	---	--

MIL-HDBK-1024/1




TITLE	DATE	FACILITY PLATE	SHEET
Joint Control Facility (High Density) Site Plan	11/92	133-74	2 Of 7


MIL-HDBK-1024/1




MIL-HDBK-1024/1



MIL-HDBK-1024/1



MIL-HDBK-1024/1



Graphic Scale in Feet  
 0 10 20 30 40

Note: See Sheet 4 Of 7 For Legend

TITLE Joint Control Facility (High Density) Building Layout - Part 2	DATE 11/92	FACILITY PLATE 133-74	SHEET 6 Of 7
--	---------------	--------------------------	-----------------

MIL-HDBK-1024/1

```

+))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))
*
*
*                               Joint Control Facility *
*
* Plumbing Requirements (GPM):           Medium           High           *
*   Water;                               Density           Density           *
*
*     Cold                               74                74                *
*     Hot
*       Recovery Rate (100 Degs. Rise)    100                100                *
*       Storage (Gal.)                    160                160                *
*   Fire Protection Requirements
*   Not Included
*
* Heating Requirements (BTU/HR x 1000): *
*   (Inside Design Temperature = 72 Degs. F) *
*   Outside Design Temperature           -5 Degs. F        490                600                *
*                                       +5 Degs. F        430                530                *
*                                       -15 Degs. F       380                460                *
*                                       -25 Degs. F       295                360                *
*
* Air Conditioning Requirements (BTU/HR x 1000): *
*   Based on 91 Degs. D.B.   76 Degs. W.B. Outside Design Conditions; *
*   Cooling Load                               1620                2140                *
*
*   Heat rejected to conditioned spaces by energized test. *
*   Equipment & parts under repair not included. *
*
* Electrical Requirements (KVA): *
*   Lights; *
*     Connected Load                           90                90                *
*     Estimated Demand                          63                63                *
*
*   Power; *
*     Connected Load                           514                610                *
*     Estimated Demand                          360                427                *
*
*   Air Conditioning; *
*     Connected Load                           377                784                *
*     Estimated Demand                          264                550                *
*
*   Total; *
*     Connected Load                           981                1484                *
*     Estimated Demand                          687                1040                *
*     Emergency Generator (KW)                  400                600                *
*
* Areas (SF): *
*   Gross area including mechanical *
*   equipment room                            33,970                39,500                *
*
*
*
*

```

```

/))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))
* TITLE                               * DATE * FACILITY PLATE * SHEET *
*   Joint Control Facility * * * *
*   Design Notes * 11/92 * 133-74 * 7 OF 7 *
.)))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))

```

MIL-HDBK-1024/1

6.3.4.1 Air Conditioning. Provide the following:

a) Two parallel piped air cooled chillers, each designed for 60 percent of the total building cooling load. Alternate operation of chillers automatically on a regular basis when load is less than 60 percent. Consider cold storage to minimize power peaks.

b) One chilled water circulation pump for each chiller plus a manifold spare pump. Design chiller circuitry so that the pump shall operate and water flow before the chiller is energized. The spare pump may be manually operated. Provide secondary chilled water loops with three-way valves at coils in each circuit to result in constant flow through chiller.

c) Divide the building into three cooling zones: administrative areas, operations areas, and the equipment areas. Provide separate air handlers and ducting systems for each zone. Provide sound attenuators for supply duct work. Consider more than one air handler for large zones.

d) Provide two air handlers for the operations, the NTDS/ACDS, and terminal distribution rooms. Design the air handler controls to regulate the units as primary and secondary with each unit alternating as the primary. Provide air handlers capable of controlling humidity, equipped with electric heat, and specifically designed for computer room applications. Refer to MIL-HDBK-1012/1.

6.3.4.2 Heating. Provide fuel oil or gas operated boiler heating system designed to accommodate the largest heating load anticipated. Provide two circulation pumps, each designed for 100 percent of the total building heating load. Design the pump controls to regulate the pumps as primary and secondary with each pump alternating as the primary.

6.3.5 Electrical Requirements

6.3.5.1 Uninterrupted Power Supply (UPS). Provide non-redundant UPS in accordance with par. 2.5.8. Use anticipated load to determine the size of UPS.

6.3.5.2 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described in par. 2.5.7. Provide emergency power to the following:

- a) Loads as required by NFPA-101.
- b) Electronic equipment in operations, the NTDS/ACDS, and equipment rooms.
- c) Building mechanical systems supporting electronic equipment.
- d) Exterior security lighting and security systems.

## MIL-HDBK-1024/1

6.3.5.3 400-Hz Power. Provide 400-Hz power for the NTDS/ACDS in accordance with par. 2.5.9.

6.3.6 Lighting. Design lighting in accordance with par. 2.5.6. Provide dimmer adjustable red lighting in the IFR room.

6.3.7 Security. The JCF is normally located within restricted areas which meet the minimum security measures for external security. If the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. Security at the main building entrance usually requires a single entry point with visitor control. Remote locks, video cameras, card readers, and/or key pads may be required by COMNISCOM as components of the IDS. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6. Provide the following:

- a) Electronic cipher door locks at access points to operations room.
- b) Exterior doors in operations, the NTDS/ACDS, equipment/maintenance, and mechanical/electrical rooms with no access hardware on the outside.
- c) CCTV.
- d) Security fencing and guard post for facilities located outside of the secure area of the Naval installation.
- e) Personnel identification, visitor check-in, and control system to control ingress and egress.

6.3.8 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

#### 6.4 Air Traffic Control Tower

6.4.1 Function. The air traffic control tower building houses equipment and personnel for visual flight rules (VFR) control of aircraft approaching and departing the terminal area or airport and aircraft and vehicular movement on the runways, taxiways, and other operation areas.

6.4.2 Tower Location and Height. Locate the air traffic control tower building on the edge of the airfield, situated to have an unobstructed line-of-sight to the aircraft approach areas, runways, taxiways, aircraft parking areas, and other operational areas over which aircraft movements are to be controlled. Provide a tower location and height to result in the tower cab eye level line of site intersecting airport traffic surfaces at a vertical

MIL-HDBK-1024/1


angle of 35 minutes or greater. Refer to FAA Order 6480.4, Airport Traffic Control Tower Siting Criteria and par. 2.2.6.

6.4.3 Architectural and Structural Requirements. See Facility Plate 141-70 (Sheets 1 through 6 of 6). The air traffic control tower is categorized as low or high density based on air traffic volume. Refer to FAA Order 6480.7, Airport Traffic Control Tower and Terminal Radar Approach Control Facility Design. Consider the use of prefabricated modular construction for tower and tower cab. Provide the following:


- a) Removable, modular, access flooring in the tower cab with 18 inches of clearance provided between the floor panels and subfloor to accommodate wiring and insulated piping. Refer to par. 2.3.5.2.
- b) Interior and exterior acoustical treatment to attain the room criteria described in par. 2.3.1.
- c) Clear span roof structure (no interior columns) in tower cab.
- d) Roof hatch to provide access to the roof from the cab floor.
- e) Floor hatch to allow moving equipment between the cab and the top elevator landing.
- f) Walkway around the exterior of the control cab to facilitate washing cab windows.
- g) Traction type elevator. Refer to NAVFAC DM-3.09 Elevators, Escalators, Dumbwaiters, Access Lifts, and Pneumatic Tube Systems, and par. 2.4.9.9.
- h) Pressure relief system to equalize interior and exterior atmospheric pressures during high wind conditions.
- i) Electrically operated, retractable covers for cab windows at sites prone to hurricane and typhoon conditions.
- j) A 2,000-pound capacity, remote controlled, electric hoist in the tower cab. Suspend hoist from tower cab roof framing.
- k) A cable raceway to cab roof through tubular cab roof columns.

6.4.3.1 Interior Walls. Provide fire-rated walls for stair enclosure, plumbing and electrical chases.


MIL-HDBK-1024/1




MIL-HDBK-1024/1




MIL-HDBK-1024/1



MIL-HDBK-1024/1



MIL-HDBK-1024/1



MIL-HDBK-1024/1

```

+))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))),
*
*                                     Air Traffic
*                                     Control Tower
*
* Plumbing Requirements:
*   Water;
*
*   Cold                               G.P.M.           12
*   Hot
*     Recovery Rate (100 Degs. Rise)  G.P.M.           20
*     Storage Gal                       20
*   Fire Protection Requirements
*   Not Included
*
* Heating Requirements (BTU/HR x 1000):
*   (Inside Design Temperature = 72 Degs. F)
*   Outside Design Temperature      -5 Degs. F       215
*                                   +5 Degs. F       185
*                                   +15 Degs. F      160
*                                   +25 Degs. F      130
*
* Air Conditioning Requirements (BTU/HR x 1000):
*   Based on 91 Degs. D.B.  76 Degs. W.B. Outside Design
*   Conditions; Cooling Load                               185
*
*   Heat rejected to conditioned spaces by energized test.
*   Equipment & parts under repair not included.
*
* Electrical Requirements (KVA):
*   Lights;
*     Connected Load                               12.0
*     Estimated Demand                             11.0
*
*   Power;
*     Connected Load                               62.0
*     Estimated Demand                             56.0
*
*   Air Conditioning;
*     Connected Load                               13.0
*     Estimated Demand                             12.0
*
*   Total;
*     Connected Load                               87.0
*     Estimated Demand                             79.0
*     Emergency Generator (KW)                    60.0
*
* Areas (SF):
*   Gross area including mechanical
*   equipment room                                   3,940
*
*
*

```

```

/))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))1
* TITLE                               * DATE * FACILITY PLATE * SHEET *
*   Air Traffic Control Tower         * 11/92 * 141-70 * 6 OF 6 *
*   Facility Design Notes             * * * *

```

## MIL-HDBK-1024/1

6.4.3.2 Windows. Do not use windows in tower structure. Provide tower cab with heat-absorbing insulated window units in accordance with NFGS-08800. Provide units with a light transmissivity of not less than 85 percent, heat transmission (U value) of 0.60 maximum, and free of parallax or other optical distortion. Provide spare window units interchangeable with any other similar unit in the tower cab. Provide window shades for tower cab windows. Refer to FAA Specification FAA-E-2470.

6.4.4 Mechanical Requirements. Use peripheral strip cooling diffusers to reduce solar impact to the personnel and wall diffusers to control tower cab temperatures.

6.4.5 Electrical Requirements

6.4.5.1 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described in par. 2.5.7. Consider a common generator when the air traffic control tower is sited adjacent to the air operations building, MTRACON, FACSFAC, JCF, or tower base building. Provide emergency power to the following:

- a) Loads as required by NFPA-101.
- b) Electronic equipment in the tower cab and communications equipment rooms.
- c) Building mechanical systems supporting electronic equipment.
- d) Exterior security lighting and security systems.

6.4.5.2 Uninterrupted Power Supply (UPS). Provide non-redundant UPS in accordance with par. 2.5.8. Use anticipated load to determine the size of UPS.

6.4.6 Lighting. Design lighting in accordance with par. 2.5.6. Provide dimmer adjustable white ceiling lights in tower cab. Provide down lighting over work areas on separate switch.

6.4.7 Fire Protection. Refer to MIL-HDBK-1008, Fire Protection for Facilities, Engineering, Design, and Construction, and NFPA 101. Consult local fire prevention agency to determine if air traffic control tower meets height criteria to be classified as a "High Rise Building."

6.4.8 Security. Air traffic control towers are normally located within restricted areas which meet the minimum security measures for external security. If the facility is located within a restricted area of a lower level of security, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6. Provide an electronic

MIL-HDBK-1024/1

cipher door lock at the first floor entrance with an intercom and remote lock release in the tower cab.

6.4.9 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

6.5 Air Traffic Control Tower Base Building

6.5.1 Function. The air traffic control tower base building provides housing for equipment and personnel to support IFR control of aircraft on approach to or departure from the terminal radar facility or airport. Other functions include ground controlled approach (GCA) or PAR for landing aircraft during inclement weather and limited visibility.

6.5.2 Location. Locate adjacent to the air traffic control tower.

6.5.3 Architectural and Structural Requirements. See Facility Plate 141-71 (Sheets 1 through 3 of 3). Provide the following:

a) Removable, modular, access flooring in the IFR and terminal equipment rooms with 18 inches of clearance provided between the floor panels and subfloor to accommodate wiring and insulated piping. Refer to par. 2.3.5.2.

b) A 9-foot clear ceiling height above accessible flooring.

c) Built-in workbenches and shelving in the terminal equipment room.

d) Facility and restroom areas readily accessible by the physically handicapped.

e) Interior and exterior acoustical treatment to attain the room criteria described in par. 2.3.1.


f) Cable troughs or conduits between the air traffic control tower and the base building for intrafacility cabling. Exact dimensions of the cable trough or size and number of conduits are specified in the BESEP.

6.5.3.1 Windows. Do not provide windows in IFR or terminal equipment rooms. Provide insulated glazing for noise reduction in administrative areas. Refer to par. 2.3.10.


6.5.4 Electrical Requirements

6.5.4.1 Uninterrupted Power Supply (UPS). Provide non-redundant UPS in accordance with par. 2.5.8. Use the anticipated load to determine the size of the UPS.

MIL-HDBK-1024/1



MIL-HDBK-1024/1



MIL-HDBK-1024/1

```

+))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))),
*
*
*                               Base Building
*
* Plumbing Requirements:
*   Water;
*
*     Cold                     G.P.M.          62
*     Hot
*       Recovery Rate (100 Degs. Rise) G.P.M.     17
*       Storage Gal              40
*   Fire Protection Requirements
*   Not Included
*
* Heating Requirements (BTU/HR x 1000):
*   (Inside Design Temperature = 70 Degs. F)
*   Outside Design Temperature   -5 Degs. F     95
*                               +5 Degs. F     85
*                               +15 Degs. F    75
*                               +25 Degs. F    65
*
* Air Conditioning Requirements (BTU/HR x 1000):
*   Based on 91 Degs. D.B.   76 Degs. W.B. Outside Design
*   Conditions; Cooling Load 275
*
*   Heat rejected to conditioned spaces by energized test.
*   Equipment & parts under repair not included.
*
* Electrical Requirements (KVA):
*   Lights;
*     Connected Load          15
*     Estimated Demand        11
*
*   Power;
*     Connected Load          65
*     Estimated Demand        46
*
*   Air Conditioning;
*     Connected Load          100
*     Estimated Demand        70
*
*   Total;
*     Connected Load          180
*     Estimated Demand        127
*     Emergency Generator (KW) 125
*
* Areas (SF):
*   Gross area including mechanical
*   equipment room           4,320
*
*
* /))))))))))))))))))))))))))))))))))))))0))))))0))))))))))))))))))))0))))))1
* TITLE                    * DATE *   FACILITY PLATE   * SHEET *
*   Air Traffic Control Tower Base * 11/92 *   141-71       * 3 OF 3 *
*   Building Facility Design Notes *     *              *      *
* .))))))))))))))))))))))))))))))))))))))2))))))2))))))))))))))))))))2)))))))-

```

MIL-HDBK-1024/1

6.5.4.2 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described par. 2.5.7. Provide emergency power to the following:

- a) Loads as required by NFPA-101.
- b) Electronic equipment in IFR and terminal equipment rooms.
- c) Building mechanical systems supporting electronic equipment.
- d) Exterior security lighting and security systems.

6.5.4.3 400-Hz Power. Provide 400-Hz power in accordance with par. 2.5.9 when required by the BESEP.

6.5.5 Lighting. Design lighting in accordance with par. 2.5.6. Provide dimmer adjustable red lights in IFR control room.

6.5.6 Security. Air traffic control tower base buildings are normally located within restricted areas which meet the minimum security measures for external security. If the facility is located within a restricted area of a lower level of security, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6. Provide the following:

- a) Electronic cipher door locks at interior entrance doors to IFR and terminal equipment rooms.
- b) Exterior doors in IFR and terminal equipment rooms with no access hardware on the outside.

6.5.7 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

MIL-HDBK-1024/1

## Section 7: METEOROLOGICAL FACILITIES

7.1 Function. Meteorological buildings provide housing for meteorological, radio and computer equipment, and personnel which provide the shore establishment and operating forces with environmental information for air, surface, and subsurface operations. Facilities are attended for 24-hour operations. Meteorological buildings comprise two basic categories: fleet weather centrals and fleet weather facilities.

7.1.1 Fleet Weather Central. The fleet weather central building provides housing for equipment and personnel which coordinates with the fleet weather facilities within its assigned area of responsibility to insure quality and continuity of services. The fleet weather central is assigned more extensive scientific, operational, and geographic responsibilities than a facility, such as computer center operations, engineering assistance, optimum track ship routing, wind and high seas warnings, and expanded communications responsibility for fleet radio facsimile and teletype broadcast. See Facility Plate 137-10 (Sheets 1 through 3 of 6).

7.1.2 Fleet Weather Facility. The fleet weather facility building provides housing for equipment and personnel to provide environmental information for local operations. See Facility Plate 137-10 (Sheets 4 through 6 of 6).


7.2 Location. The location of the meteorological building is established by the ordering authority and defined by instructions from Naval Oceanographic Office I.C. (NAVOCEANO). Normally, these buildings will be located at a Naval installation in the operations complex.

7.3 Architectural and Structural Requirements. See Facility Plate 137-10 (Sheets 1 through 6 of 6). Provide the following:


- a) Removable, modular, access flooring in the computer and operations rooms with 18 inches of clearance provided between floor panels and subfloor to accommodate wiring and insulated piping. Refer to par. 2.3.5.2.
- b) Service counters at electronic display and reception/weather information areas.
- c) Central passage corridors a minimum of 6 feet wide and clear of obstructions.
- d) Clear ceiling height of 9 feet above finished floor.
- e) Facility and restrooms readily accessible by the physically handicapped.

7.3.1 Overhead Doors. Provide manually operated overhead door for maintenance and mechanical/electrical room.

MIL-HDBK-1024/1




MIL-HDBK-1024/1






MIL-HDBK-1024/1



MIL-HDBK-1024/1





MIL-HDBK-1024/1

7.4 Electrical Requirements

7.4.1 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described in par. 2.5.7. Provide emergency power to the following:

- a) Loads as required by NFPA-101.
- b) Exterior security lighting and security systems.
- c) Electronic equipment in operations, computer, and communications rooms.
- d) Building mechanical systems supporting electronic equipment.

7.4.2 Uninterrupted Power Supply (UPS). Provide non-redundant UPS in accordance with par. 2.5.8. Use the anticipated load to determine the size of the UPS.

7.5 Security. Meteorological facilities are normally located within restricted areas which meet the minimum security measures for external security. If the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6.

7.6 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

MIL-HDBK-1024/1

## Section 8: SPECIAL SUPPORT FACILITIES

8.1 Air Operations Building

8.1.1 Function. The air operations building houses the administration of flight operational activities with supporting functions including, but not limited to, airfield control, flight support, flight planning, flight scheduling, safety, transient aircraft services, weather station, search and rescue, and administrative functions.

8.1.2 Location. Locate the air operations building on the edge of the airfield adjacent to the air traffic control tower and the MTRACON facility where siting requirements permit. Refer to MIL-HDBK-1021/1, Airfield Geometric Design and par. 2.2.6.

8.1.3 Architectural and Structural Requirements. See Facility Plate 141-40 (Sheets 1 through 4 of 4). Provide the following:

- a) Service counters at flight clearance and weather briefing areas.
- b) Central passage corridors a minimum of 6 feet wide and clear of obstructions.
- c) Hydraulic passenger elevator with removable protective padding for transporting equipment. Refer to NAVFAC DM-3.09 and par. 2.4.9.9.
- d) Access/exit stairs.
- e) Facility and restrooms readily accessible by the physically handicapped.


8.1.3.1 Windows. Provide insulated glazing for noise reduction in administrative areas. Refer to par. 2.3.10.

8.1.4 Electrical Requirements


8.1.4.1 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described in par. 2.5.7. Provide emergency power to the following:

- a) Loads as required by NFPA-101.
- b) Exterior security lighting.
- c) Electronic equipment designated as mission critical.
- d) Building mechanical systems supporting mission critical electronic equipment.


MIL-HDBK-1024/1



MIL-HDBK-1024/1




MIL-HDBK-1024/1



**LEGEND**

- 201 Storage
- 202 Aviation Safety
- 203 Flight Support
- 204 Flight Schedules
- 205 Air Operations Admin
- 206 Asst. Air Operations Officer
- 207 Air Operations Officer
- 208 Briefing Room
- 209 Men's Lockers
- 210 Men's Rest./Shower
- 211 Janitor/Storage
- 212 Janitor
- 213 Women's Rest./Shower
- 214 Women's Lockers
- 215 Training
- 216 Leading Chief Petty Officer/Records
- 217 Storage

**SECOND FLOOR PLAN**



TITLE	DATE	FACILITY PLATE	SHEET
Air Operations Building Second Floor Layout	11/92	141-40	3 OF 4

MIL-HDBK-1024/1

```

+)))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))
*
*
*                      Air Operations
*
* Plumbing Requirements (GPM):
*   Water;
*
*     Cold                      89
*     Hot
*       Recovery Rate (100 Degs. Rise)    45
*       Storage (Gal)                     200
* Fire Protection Requirements
*   Not Included
*
* Heating Requirements (BTU/HR x 1000):
*   (Inside Design Temperature = 72 Degs. F)
*   Outside Design Temperature      -5 Degs. F    400
*                                   +5 Degs. F    345
*                                   +15 Degs. F   295
*                                   +25 Degs. F   245
*
* Air Conditioning Requirements (BTU/HR x 1000):
*   Based on 91 Degs. D.B.   76 Degs. W.B. Outside Design
*   Conditions; Cooling Load                      540
*
*   Heat rejected to conditioned spaces by energized test.
*   Equipment & parts under repair not included.
*
* Electrical Requirements (KVA):
*   Lights;
*     Connected Load                      42.0
*     Estimated Demand                    34.0
*
*   Power;
*     Connected Load                      19.0
*     Estimated Demand                    16.0
*
*   Air Conditioning;
*     Connected Load                      92.0
*     Estimated Demand                    74.0
*
*   Total;
*     Connected Load                      153.0
*     Estimated Demand                    124.0
*
* Emergency Generator (KW)                      30.0
*
* Areas (SF):
*   Gross area including mechanical
*   equipment room                            12,637
*
* General Notes:
*
/))))))))))))))))))))))))))))))))))))))))))0))))))0))))))))0))))))1
* TITLE                                         * DATE * FACILITY PLATE * SHEET *
* Air Operations Building                       * 11/92 *           141-40 * 4 OF 4 *
* Facility Design Notes                        *     *                   *     *
.))))))))))))))))))))))))))))))))))))))2))))))2))))))))2)))))))-
    
```

MIL-HDBK-1024/1

8.1.5 Security. Air operations buildings are normally located within restricted areas which meet the minimum security measures for external security. If the facility is located within a restricted area of a lower level of security, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements shall be designated in the IDSEP. Refer to par. 2.6.

8.1.6 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

## 8.2 Fleet Reconnaissance Photographic Laboratory

8.2.1 Function. The fleet reconnaissance photographic laboratory supports photo reconnaissance squadrons assigned to fleet support stations. The laboratory provides administrative and technical space for processing aerial film, preparation of mosaics, and application of photogrammetry and photographic intelligence. The laboratory provides housing for processing equipment, film, supplies, camera and equipment repair, and training, and may also provide passport and permit photographic services.

8.2.2 Location. Locate the fleet reconnaissance photographic laboratory as a stand-alone facility adjacent or in proximity to the operational reconnaissance squadron.


8.2.3 Architectural and Structural Requirements. See Facility Plate 141-65 (Sheets 1 through 3 of 3). Provide the following:

- a) Floor drainage for equipment in processing, reproduction, enlarging and finishing areas.
- b) Light-trap doors for darkrooms.
- c) Secure film storage vaults.
- d) Built-in furnishings including counters, storage compartments, and shelving. Provide counter and shelf finishes resistant to photographic processing chemicals.
- e) Eye and body wash stations.
- f) Facility and restroom areas readily accessible by the physically handicapped.


8.2.3.1 Floors. Provide the following:

- a) Floors in storage areas designed for the weight of the storage canisters.

MIL-HDBK-1024/1



MIL-HDBK-1024/1





## MIL-HDBK-1024/1

b) Chemical resistant floor covering in storage, supply, finishing, and processing areas.

8.2.3.2 Light-Trap Doors. Provide revolving or similar light-trap doors specifically designed for film developing areas.

#### 8.2.4 Mechanical Requirements

8.2.4.1 Heating and Air Conditioning. Design thermostatically controlled heating and air conditioning systems to provide the following conditions:

a) Temperatures:

Film Processing Areas	70 to 80 degrees F
Printing/Finishing Operation	70 to 75 degrees F

b) Relative Humidity:

Film Processing Areas	50 percent maximum
Printing/Finishing Operation	50 to 60 percent

8.2.4.2 Ventilation. Provide the following:

a) Filtered air intake and interior return vents.

b) Minimum air movement, approximately 15 feet per minute, within ventilation system to prevent agitation of settled dust.

c) Ventilation within film processing and chemical storage areas in accordance with Industrial Ventilation: A Manual of Recommended Practice.

8.2.4.3 Plumbing. Provide the following:

a) Filtered and thermostatically temperature controlled water for processing area and categorized for developers, machine washing, and machine processing.

b) Acid resistant waste lines.

c) Waste lines from processors and sinks routed to silver nitrate recovery area.

#### 8.2.5 Electrical Requirements

8.2.5.1 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described in par. 2.5.7. Provide emergency power to the following:

a) Loads required by NFPA-101.

MIL-HDBK-1024/1

b) Air conditioning, ventilation, processing equipment, and supply refrigerators.

c) Exterior security lighting.

8.2.6 Security. Fleet reconnaissance photographic laboratories are normally located within restricted areas which meet the minimum security measures for external security. If the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements shall be designated in the IDSEP. Refer to par. 2.6.

8.2.7 Hazardous Waste Storage. Provide space for hazardous materials containers in the supply room. Provide storage for hazardous wastes in a covered outdoor, water sealed concrete containment. Design the containment to hold a spill equal to the largest container plus 10 percent and the waste containers. Provide a fence and signs stating "Hazardous Waste Storage."

8.2.8 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

8.3 Anti-Submarine Warfare Operations Center (ASWOC)

8.3.1 Function. The ASWOC building houses the Navy Command and Control Systems (NCCS) which provide the anti-submarine warfare (ASW) sector commander with the facilities and capabilities to plan and execute assigned missions, which include ASW, anti-surface warfare (ASUW), over the horizon targeting (OTHT), maritime surveillance, mining, search and rescue, drug enforcement operations, special projects, power projection, battle group/amphibious task force/convoy support, and flight crew training. ASWOCs operate across the entire threat environment from peacetime surveillance through low intensity conflict/regional contingency operations to general war.


8.3.2 Location. Locate the ASWOC building adjacent to the Naval Oceanography Command (NAVOCEANCOM) and Special Information Command (SPINTCOM) activities and as close as possible to the patrol squadron hangar. Locate within 1,000 feet of a suitable site for a AN/SMQ-11 antenna.

8.3.3 Architectural and Structural Requirements. See Facility Plate 141-42 (Sheets 1 through 7 of 7). Provide the following:


a) A one- or two-story building.

b) Blast hardened construction. Refer to NAVFAC P-397, Structures to Resist the Effects of Accidental Explosions; DM-2.08, Blast Resistant Structures; and MIL-HDBK-1013/1.

MIL-HDBK-1024/1




MIL-HDBK-1024/1




<p>TITLE ASWOC Two-Story Facility Site Plan</p>	<p>DATE 11/92</p>	<p>FACILITY PLATE 141-42</p>	<p>SHEET 2 Of 7</p>
---	-----------------------	----------------------------------	-------------------------


MIL-HDBK-1024/1



MIL-HDBK-1024/1



MIL-HDBK-1024/1





MIL-HDBK-1024/1

```

+)))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))
*
*
* Plumbing Requirements:  G.P.M.
*   Water;
*
*   Cold                65                65
*   Hot
*   Recovery Rate (100 Degs. Rise)    45                60
*   Storage Gal                100                65
*   Fire Protection Requirements
*   Not Included
*
* Heating Requirements (BTU/HR x 1000):
* (Inside Design Temperature = 72 Degs. F)
* Outside Design Temperature
*   -5 Degs. F    485                650
*   +5 Degs. F    420                570
*   -15 Degs. F   360                485
*   -25 Degs. F   300                400
*
* Air Conditioning Requirements (BTU/HR x 1000):
* Based on 91 Degs. D.B.   76 Degs. W.B.  Outside Design Conditions;
* Cooling Load                825                1015
*
* Heat rejected to conditioned spaces by energized test.
* Equipment & parts under repair not included.
*
* Electrical Requirements (KVA):
* Lights;
*   Connected Load                64.0                74.0
*   Estimated Demand              52.0                59.0
*
* Power;
*   Connected Load                289.0               245.0
*   Estimated Demand              191.0               196.0
*
* Air Conditioning;
*   Connected Load                302.0               372.0
*   Estimated Demand              242.0               298.0
*
* Total;
*   Connected Load                605.0               691.0
*   Estimated Demand              485.0               553.0
*
* Emergency Generator (KW) (Two Required)    600.0 Ea.    600.0 Ea.
*
* Areas (SF):
* Gross area including mechanical
* equipment room                21,275          23,644
*
* General Notes:
*
*
/))))))))))))))))))))))))))))))))))))))0))))))))0))))))))0))))))1
* TITLE                            * DATE    * FACILITY PLATE    * SHEET *
* ASWOC Facility Design Notes * 11/92   * 141-42            * 7 OF 7 *
.)))))))))))))))))))))))))))))))))))2))))))))2))))))))2)))))))-

```

MIL-HDBK-1024/1

c) RF shielding throughout the facility. Refer to MIL-HDBK-1195 and NAVFAC Instruction 11010.44. Shielding requirements shall be confirmed by NESSEC.

d) High altitude electromagnetic pulse (HEMP) hardening for the rectangular area bounded by Analysis, Intelligence Officer, ASWOC Support Communications (ASCOMM), automatic data processing (ADP), and the UPS room. Use stainless steel for 100 dB protection. Refer to DM-12.02, High Altitude Electromagnetic Pulse Protection for Ground-Based Facilities.

e) Built-in furnishings including counters, benches, service windows, and storage racks.

f) Passage corridors a minimum of 5 feet, 6 inches wide and clear of obstructions.

g) Removable, modular, access flooring in the operations control, mission control and evaluation, ADP and analysis rooms with 18 inches of clearance provided between the floor panels and subfloor to accommodate wiring and insulated piping. Refer to par. 2.3.5.2.

h) Hydraulic passenger elevator with removable protective padding for transporting equipment (two-story facility only). Refer to NAVFAC DM-3.09 Elevators, Escalators, Dumbwaiters, Access Lifts, and Pneumatic Tube Systems, and par. 2.4.9.9.

i) Access/exit stairs.

j) Facility and restroom areas readily accessible by the physically handicapped.

8.3.3.1 Windows. Do not use windows unless specifically requested for administration areas.

8.3.4 Mechanical Requirements. Design a thermostatically controlled heating and air conditioning system to meet the criteria in pars. 2.4 and 8.3.4.1.

8.3.4.1 Ventilation. Provide ventilation for UPS and battery rooms in accordance with par. 2.4. Provide ozone removal for analysis room by ventilation to atmosphere.

8.3.5 Electrical Requirements

8.3.5.1 Uninterrupted Power Supply (UPS). Provide non-redundant UPS in accordance with par. 2.5.8. Use anticipated load to determine the size of the UPS.

MIL-HDBK-1024/1

8.3.5.2 Emergency Electrical Power. Provide two 600 kW emergency generators (primary and backup) with automatic starting and switching capability as described in par. 2.5.7. Provide emergency power to the following:

- a) Loads as required by NFPA-101.
- b) Electronic equipment in the operations control, mission evaluation and control, ADP, analysis, and communications rooms.
- c) Building mechanical systems supporting electronic equipment.
- d) Exterior security lighting and security systems.

8.3.6 Security. ASWOCs are normally located within restricted areas which meet the minimum security measures for external security. If the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements shall be designated in the IDSEP. Refer to par. 2.6. Provide the following:

- a) Secured access restrictors in HVAC ducting.
- b) Classified material mulching machine.
- c) External and internal surveillance television cameras and monitors.
- d) Electronic cipher door locks at entry doors.

8.3.7 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

#### 8.4 Air Cargo Terminal

8.4.1 Function. The air cargo terminal houses equipment and personnel for handling and movement of material including, but not limited to, receipt of packages, control documentation, palletization, holding for shipment, aircraft loading and unloading, package sorting, and loading on trucks. Air cargo terminals, to the maximum degree feasible, are mechanized and, where justified, automated, and computer controlled.

8.4.2 Location. Locate the air cargo terminal as a stand-alone facility or combined with the air passenger terminal on the apron line in reasonable proximity to the air operations building. Refer to MIL-HDBK-1021/1 and par. 2.2.6.

MIL-HDBK-1024/1

8.4.3 Architectural and Structural Requirements. The facilities are designated as small or medium/large buildings. See Facility Plate 141-12 (Sheets 1 through 5 of 5). Provide the following:

- a) Forklift charging stations.
- b) Ball bearing pallet platform in medium/large building.
- c) Clear ceiling height of 16 feet in cargo handling area with overhead doors open.
- d) Dust pickup, conveying, and collection system in carpentry shop.
- e) Weighing scales.
- f) Overhead hoist (capacity determined by user).
- g) Compressed air system (capacity determined by user).
- h) Built-in furnishings including counters, benches, and storage racks.
- i) Administration and personnel spaces with one-hour fire separation from cargo/work areas.
- j) Facility and restroom areas readily accessible by the physically handicapped.
- k) Additional area to accommodate storage of malfunctioning equipment.

8.4.3.1 Structure. Design roof framing system to support suspended equipment and overhead hoist.

8.4.3.2 Wire Mesh Partitions. Construct wire mesh partitions with doors for security cage. Refer to NFGS-10605, Wire Mesh Partitions.


8.4.3.3 Interior Doors. Provide insulated doors between personnel spaces and cargo handling areas.

8.4.3.4 Overhead Doors. Provide electrically operated overhead doors.

8.4.3.5 Pre-engineered Buildings. Consider using a pre-engineered metal building. Refer to NFGS-13121, Pre-engineered Metal Buildings (Rigid Frame).


8.4.4 Mechanical Requirements

MIL-HDBK-1024/1




<p>TITLE Air Cargo Terminal (Small) Facility Site Plan</p>	<p>DATE 11/92</p>	<p>FACILITY PLATE 141-12</p>	<p>SHEET 1 OF 5</p>
--	-----------------------	----------------------------------	-------------------------

MIL-HDBK-1024/1




TITLE	DATE	FACILITY PLATE	SHEET
Air Cargo Terminal (Medium/Large) Facility Site Plan	11/92	141-12	2 OF 5

MIL-HDBK-1024/1



MIL-HDBK-1024/1





MIL-HDBK-1024/1

8.4.4.1 Heating. Provide heating in accordance with par. 2.4. Design heating system for a minimum infiltration rate of two air changes per hour in cargo handling area. This rate depends on the installation of insulation seals on the overhead doors. Ensure the temperature of the cargo handling areas is thermostatically controlled for a minimum of 55 degrees F with the doors closed and 50 degrees F with the doors open.

8.4.4.2 Ventilation. Provide ventilation in accordance with par. 2.4. Provide roof-mounted ventilation fans for the cargo handling area.

8.4.4.3 Sawdust Collection and Control. Provide dust pickup, conveying, and collection system for carpenters shop. Refer to Title 29, CFR Part 1910.265, Sawmills and Industrial Ventilation: A Manual of Recommended Practice.

8.4.4.4 Fire Protection. Provide fire protection for the carpenter's shop in accordance with NFPA 664, Prevention of Fires and Explosions in Wood Processing and Woodworking Facilities.

8.4.5 Electrical Requirements

8.4.5.1 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described in par. 2.5.7. Provide emergency power to the following:

- a) Loads required by NFPA 101.
- b) Exterior security lighting.

8.4.6 Lighting. Design lighting in accordance with par. 2.5.6. Provide high-pressure sodium vapor lighting in cargo/work areas.

8.4.7 Security. Air cargo terminals are normally located within restricted areas which meet the minimum security measures for external security. If the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area, provide additional measures to meet minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6.

8.4.8 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

8.5 Air Passenger Terminal

8.5.1 Function. The air passenger terminal houses equipment and personnel for processing authorized air passengers and their baggage and for handling incidental freight including unpalletized general cargo.

MIL-HDBK-1024/1

8.5.2 Location. Locate the air passenger terminal on the apron line as a stand-alone facility or combined with the air operations building or the air cargo building. When not combined with air operations building, locate in reasonable proximity to the air operations building. Refer to par. 2.2.6 and MIL-HDBK-1021/1.

8.5.3 Architectural and Structural Requirements. See Facility Plate 141-11 (Sheets 1 through 3 of 3). Provide the following:

- a) Baggage conveyors for baggage check-in and claim areas.
- b) Security vault accessed from reserved waiting lounge.
- c) Kitchenette accessed from reserved waiting lounge.
- d) Pay telephone stations and concession areas.
- e) Passenger security screening and baggage x-ray equipment.
- f) A separate holding area for security cleared passengers.
- g) Built-in furnishings including information and check-in counters.
- h) Space for infant changing area in men's and women's restrooms.
- i) Interior layout and design to provide quiet and active waiting areas.
- j) Storefront type windows and doors at terminal main entrances.
- k) Public address and passenger paging system.
- l) Facility and restroom areas readily accessible by the physically handicapped.

8.5.3.1 Wire Mesh Partitions. Construct wire mesh partition with door for detention area. Refer to NFGS-10605.


8.5.3.2 Ceilings. Consider an architecturally exposed structural ceiling.

8.5.3.3 Overhead Doors. Provide electrically operated overhead doors.


8.5.3.4 Windows. Provide insulated glazing for noise reduction. Refer to par. 2.3.10.

8.5.3.5 Pre-engineered Buildings. Consider using a pre-engineered metal building. Refer to NFGS-13121.

MIL-HDBK-1024/1



MIL-HDBK-1024/1



MIL-HDBK-1024/1

```

+)))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))
*
*
*                                     Air Passenger Terminal
*
*   Plumbing Requirements:   G.P.M.
*   Water;
*
*       Cold                                   80
*       Hot
*           Recovery Rate (100 Degs. Rise)   42
*           Storage (Gal)                    100
*   Fire Protection Requirements
*   Not Included
*
*   Heating Requirements (BTU/HR x 1000):
*   (Inside Design Temperature = 72 Degs. F)
*   Outside Design Temperature   -5 Degs. F   400
*                                   +5 Degs. F   350
*                                   +15 Degs. F  300
*                                   +25 Degs. F  250
*
*   Air Conditioning Requirements (BTU/HR x 1000):
*   Based on 91 Degs. D.B.   76 Degs. W.B. Outside Design
*   Conditions; Cooling Load   550
*
*   Heat rejected to conditioned spaces by energized test.
*   Equipment & parts under repair not included.
*
*   Electrical Requirements (KVA):
*   Lights;
*       Connected Load               9.0
*       Estimated Demand              7.0
*
*   Power;
*       Connected Load                16.0
*       Estimated Demand              13.0
*
*   Air Conditioning;
*       Connected Load                202.0
*       Estimated Demand              162.0
*
*   Total;
*       Connected Load                227.0
*       Estimated Demand              182.0
*
*   Areas (SF):
*   Gross area including mechanical
*   equipment room                   10,400
*

```

```

/))))))))))))))))))))))))))))))))))))))0))))0))))))))))))))))0)))))) 1
* TITLE                               * DATE   * FACILITY PLATE * SHEET *
*   Air Passenger Terminal Facility    * 11/92 *       141-11   * 3 OF 3 *
*   Design Notes                       *     *               *     *
.)))))))))))))))))))))))))))))))))))))2))))2))))))))))))))))2)))))) -

```

## MIL-HDBK-1024/1

8.5.4 Electrical Requirements

8.5.4.1 Emergency Electrical Power. Emergency generator is not required.

8.5.5 Security. Air passenger terminals are normally located within restricted areas which meet the minimum security measures for external security. If the facility is located within a restricted area of a lower level of security or is located remote and outside of an established restricted area, provide additional measures to meet the minimum security requirements for the level of security assigned to the facility. The level of security and the designer's responsibility for particular security elements will be designated in the IDSEP. Refer to par. 2.6.

8.5.6 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

## 8.6 Aircraft Fire and Rescue Station and Combined Structural/Aircraft Fire and Rescue Station


8.6.1 Function. Fire and rescue stations provide housing for firefighting and rescue equipment and personnel.

8.6.2 Location. Locate as close as possible to the centroid of runway operations to minimize travel time to probable rescue sites and other areas such as aprons, hardstands, and hangars where aircraft fires may occur. Refer to par. 2.2.6 and MIL-HDBK-1021/1. Ready access from the aircraft fire and rescue station to all parts of the installation is necessary to permit assistance by fire/rescue vehicles when needed to control structural fires. Where the aircraft fire and rescue station is combined with the structural fire station, provide the latter with unobstructed access to all parts of the installation keeping intersections with other vehicular or pedestrian arteries to a minimum.

8.6.3 Architectural and Structural Requirements. Fire and rescue equipment housed in the station vary with the mission of the installation and depend on the gross weight of the aircraft supported. The facilities are divided into Class A and Class B for size distinction and are provided in a one-story structure. The number of fire apparatus stalls is determined locally and may include fire trucks and crash rescue equipment. Expansion of the apparatus area (crash rescue) for storage of aircraft lifting slings may be required. The amount of storage required is based on the size, type, and number of slings for the aircraft supported, and the local or regional rescue mission assignment. See Facility Plate 141-20 (Sheets 1 through 4 of 4) and Facility Plate 141-25 (Sheets 1 through 3 of 3). Provide the following:

a) Ceiling height in the apparatus area, unobstructed, with the doors open: the greater of 16 feet or 7 feet above the tallest vehicle.


MIL-HDBK-1024/1




Not to Scale

TITLE	DATE	FACILITY PLATE	SHEET
Aircraft Fire And Rescue Station (Class A & B) Site Plan	11/92	141-20	1 of 4

MIL-HDBK-1024/1



MIL-HDBK-1024/1




MIL-HDBK-1024/1

```


+)))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))))
*
*
*
*
* Aircraft Fire And Rescue Station Type
* Plumbing Requirements (GPM):
*   Water;
*   Cold
*   Hot
*   Recovery Rate (100 Degs. Rise)
*   Storage (Gal)
* Fire Protection Requirements
*   Not Included
*
* Heating Requirements (BTU/Hr x 1000):
* Inside Design Temperature:-Personnel Support Area=72 Degs. F
*   -Aparatus Area(s)=55 Degs. F
* Outside Design Temperature
*   -5 Degs. F
*   +5 Degs. F
*   +15 Degs. F
*   +25 Degs. F
*
* Air Conditioning Requirements (BTU/Hr x 1000):
* Based on 91 Degs. D.B. 76 Degs. W.B. Outside Design Conditions;
* Cooling Load
*
* Heat rejected to conditioned spaces by energized test.
* Equipment & parts under repair not included.
*
* Electrical Requirements (KVA):
* Lights;
* Connected Load
* Estimated Demand
*
* Power;
* Connected Load
* Estimated Demand
*
* Air Conditioning;
* Connected Load
* Estimated Demand
*
* Total;
* Connected Load
* Estimated Demand
*
* Emergency Generator (KW):
*
* Areas (SF):
* Gross area including mechanical
* equipment room
*
* General Notes:
* Apparatus stall depth is based on a vehicle length of 36 feet.
* Increase the stall depth for longer vehicles.
/))))))))))))))))))))))))))))))))))))))))))0))))))0))))))))))))))))0))))))1
*TITLE Aircraft Fire And Rescue Station * DATE * FACILITY PLATE * SHEET *
* (Class A & B) Facility Design Notes* 11/92 * 141-20 * 4 OF 4 *
.)))))))))))))))))))))))))))))))))))))))))))2))))))2))))))))))))))))2))))))-

```

MIL-HDBK-1024/1



MIL-HDBK-1024/1





MIL-HDBK-1024/1

- b) Corridors a minimum of 5 feet wide and clear of obstructions.
- c) Storage for firefighting gear equal to 4 square feet per fire fighter.
- d) A one-ton capacity, electrically controlled hoist. Provide hoist rails to permit one hoist to service vehicle bays.
- e) Door guards to protect door jambs from vehicle damage.
- f) An overhead storage tank for aqueous film forming foam (AFFF). Provide storage capacity equal to twice assigned AFFF capacity of vehicles.
- g) Space for hose drying (when required).
- h) Space for refilling breathing air apparatus.
- i) Administrative and bunk areas with one-hour fire separation from the apparatus area.
- j) The alarm and mechanical rooms with 2-hour fire separation from other areas.
- k) Facility areas serving non-firefighting personnel readily accessible by the physically handicapped.

8.6.3.1 Interior Walls. Provide the following:

- a) Impervious and sufficiently smooth walls in apparatus area for easy cleaning.
- b) Demountable partitions for space separation in bunk rooms.
- c) A folding partition between dining area and dayroom.

8.6.3.2 Floors. Design apparatus area floor in accordance with NAVFAC DM-5.04 for the critical wheel load of the apparatus to be housed. Slope floor toward trench drains and overhead doors. Seal concrete floor in apparatus area.

8.6.3.3 Interior Doors. Provide insulated doors between personnel spaces and apparatus areas.

8.6.3.4 Overhead Doors. Provide electrically operated doors in apparatus area. Provide manually operated doors in maintenance shop and storage rooms.

8.6.4 Mechanical Requirements

8.6.4.1 Heating. Provide heating in accordance with par. 2.4.

MIL-HDBK-1024/1

a) Design heating system for an infiltration rate of two air changes per hour in apparatus area. This rate depends on the installation of insulation seals on the overhead doors. Ensure the temperature of the apparatus areas is thermostatically controlled for a minimum of 55 degrees F.

b) Provide a switch activated by opening the overhead doors to override the space thermostat to stop the heating equipment in the apparatus area. Provide a minimum temperature thermostat field set at 34 degrees F to override the heating deactivation switch during door-open periods of subfreezing ambient temperatures. After the doors are closed, the space thermostat should resume control. Design for heating systems recovery time of 30 minutes after the doors are closed.

8.6.4.2 Ventilation. Provide roof-mounted ventilation fans for the apparatus areas. Provide direct connections for outdoor discharge of exhaust in areas where vehicle idling is anticipated.

8.6.4.3 Plumbing. Provide hose connections in the apparatus areas for refilling vehicle water tanks. Provide trench drains with sufficient laterals for aeration and easy clean out of oil and other residue.

#### 8.6.5 Electrical Requirements

8.6.5.1 Emergency Electrical Power. Provide an emergency generator with automatic starting and switching capability as described in par. 2.5.7. Provide emergency power to the following:

- a) Loads required by NFPA-101.
- b) Exterior security lighting.
- c) Station fire alarm.

8.6.6 Pavement. Design access pavement, ready apron, and cleanup apron in accordance with NAVFAC DM-5.04 and MIL-HDBK-1021/2, General Concepts for Airfield Pavement Design, for the critical wheel load of the apparatus to be housed at the station. Provide reinforced concrete ready apron and cleanup apron. Provide continuous access pavement to the roadway/taxiway system. Slope cleanup apron to drain into wash-down runoff collection system.

8.6.7 Drainage. Provide site drainage in accordance with par. 2.2.4. Separate the collection system for trench drains and cleanup apron from the site drainage system. Treat runoff collected from cleanup apron and trench drains in accordance with MIL-HDBK-1005/9, Industrial and Oily Wastewater Control.

MIL-HDBK-1024/1

8.6.8 Security. Aircraft fire and rescue stations are normally located within the airfield security area. Provide the minimum security measures for points of ingress and egress compatible with the level of security in which the facility is located. Refer to par. 2.6.

8.6.9 Additional Design Criteria. Refer to Section 2 for facility design requirements not addressed above.

MIL-HDBK-1024/1

## REFERENCES

NOTE: THE FOLLOWING REFERENCED DOCUMENTS FORM A PART OF THIS HANDBOOK TO THE EXTENT SPECIFIED HEREIN. USERS OF THIS HANDBOOK SHOULD REFER TO THE LATEST REVISIONS OF CITED DOCUMENTS UNLESS OTHERWISE DIRECTED.

FEDERAL/MILITARY SPECIFICATIONS, STANDARDS, BULLETINS, HANDBOOKS, AND NAVFAC GUIDE SPECIFICATIONS:

Unless otherwise indicated, copies are available from the Defense Printing Service, Standardization Document Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094. Army Technical Manuals are available from the Commander, U.S. Army Publications Distribution Center, 1655 Woodson Road, St. Louis, MO 63114.

## MILITARY SPECIFICATIONS

MIL-F-29046	General Specifications for Raised Flooring
MIL-P-43607	Padlock, Key Operated, High Security, Shrouded Shackle

## FEDERAL SPECIFICATIONS

RR-F-191	Wire Fencing (Chain-Link Fabric)
----------	----------------------------------

## MILITARY STANDARDS

MIL-STD-461	Electromagnetic Emission and Susceptibility Requirements for the Control of Electromagnetic Interference
MIL-STD-882	System Safety Program Requirements
MIL-STD-1472	Human Engineering Design Criteria for Military Systems, Equipment, and Facilities

## BULLETINS

MIL-BUL-34	Engineering and Design Criteria for Navy Facilities
------------	---

## HANDBOOKS

MIL-HDBK-419	Grounding, Bonding, and Shielding for Electronic Equipment and Facilities Applications
MIL-HDBK-1001/2	Materials and Building Components

MIL-HDBK-1024/1

MIL-HDBK-1001/5	Roofing and Waterproofing
MIL-HDBK-1002 Series	Structural Engineering
MIL-HDBK-1002/2	Structural Engineering - General
MIL-HDBK-1004 Series	Electrical Engineering
MIL-HDBK-1004/1	Electrical Engineering - Preliminary Design Considerations
MIL-HDBK-1004/5	400-Hz Medium-Voltage Conversion/Distribution and Low-Voltage Utilization Systems
MIL-HDBK-1004/6	Lightning Protection
MIL-HDBK-1004/7	Wire Communications and Signal Systems
MIL-HDBK-1005/3	Drainage Systems
MIL-HDBK-1005/9	Industrial and Oily Wastewater Control
MIL-HDBK-1008	Fire Protection for Facilities, Engineering, Design, and Construction
MIL-HDBK-1012/1	Electronic Facilities Engineering
MIL-HDBK-1013/1	Design Guidelines for Physical Security of Fixed Land-Based Facilities
MIL-HDBK-1013/10	Design Guidelines for Security Fencing, Gates, Barriers, and Guard Facilities
MIL-HDBK-1021/1	Airfield Geometric Design
MIL-HDBK-1021/2	General Concepts for Airfield Pavement Design
MIL-HDBK-1190	Facility Planning and Design Guide
MIL-HDBK-1195	Radio Frequency Shielded Enclosures

## NAVFAC GUIDE SPECIFICATIONS

NFGS-03300	Cast-in-Place Concrete
NFGS-04200	Unit Masonry
NFGS-08331	Rolling Service and Fire Doors

MIL-HDBK-1024/1

NFGS-08360	Sectional Overhead Doors
NFGS-08367	Vertical Lift Metal Doors
NFGS-08510	Steel Windows
NFGS-08520	Aluminum Windows
NFGS-08529	Aluminum Storm Windows
NFGS-08710	Finish Hardware
NFGS-08800	Glazing
NFGS-09100	Metal Support Systems
NFGS-09200	Lathing
NFGS-09212	Plastering and Stuccoing
NFGS-09215	Veneer Plaster
NFGS-09250	Gypsum Board
NFGS-09310	Ceramic Tile, Quarry Tile, and Paver Tile
NFGS-09500	Acoustical Treatment
NFGS-09660	Resilient Tile Flooring
NFGS-09665	Sheet Vinyl Flooring
NFGS-09680	Carpet
NFGS-09900	Painting
NFGS-10270	Access Flooring
NFGS-10605	Wire Mesh Partitions
NFGS-13121	Pre-engineered Metal Buildings (Rigid Frame)
NFGS-16306	400-Hertz (Hz) Solid State Frequency Converter

NAVY MANUALS, P-PUBLICATIONS, DRAWINGS, AND MAINTENANCE OPERATING MANUALS:

DESIGN MANUALS

DM-1.03	Architectural Acoustics
---------	-------------------------

MIL-HDBK-1024/1

DM-2.08	Blast Resistant Structures
DM-3.01	Plumbing Systems
DM-3.03	Heating, Ventilating, Air Conditioning, and Dehumidifying Systems
DM-3.09	Elevators, Escalators, Dumbwaiters, Access Lifts, and Pneumatic Tube Systems
DM-3.10	Noise and Vibration Control for Mechanical Equipment
DM-5.04	Pavements
DM-12.02	High Altitude Electromagnetic Pulse Protection for Ground-Based Facilities
DM-13.02	Commercial Intrusion Detection Systems (IDS)
DM-22	Petroleum Fuel Facilities
DM-28.04	General Maintenance Facilities

P-PUBLICATIONS

P-80	Facility Planning Criteria for Navy and Marine Corps Shore Installations
P-80.3	Facility Planning Factor Criteria for Navy and Marine Corps Shore Installations, Appendix E: Airfield Safety Clearances
P-89	Engineering Weather Data
P-355	Seismic Design for Buildings
P-397	Structures to Resist the Effects of Accidental Explosions
P-442	Economic Analysis Handbook

NAVELEX PUBLICATIONS

NAVELEX 0101,107	Naval Shore Electronics Criteria
------------------	----------------------------------



MIL-HDBK-1024/1

Title 40 CFR Part 114 Civil Penalties for Violation of Oil Pollution Prevention Regulations

Title 40 CFR Part 280 Underground Storage Tanks Technical Requirements

(Unless otherwise indicated, copies are available from the Superintendent of Documents, U.S. Government Printing Office (GPO), Washington, D.C. 20402.)

FAA AC 70/7460	Obstruction Marking and Lighting
FAA AC 150/5300-13	Airport Design
FAA Order 6310.6	Primary/Secondary Terminal Radar Siting Handbook
FAA Order 6340.15	Primary/Secondary En Route Radar Siting Handbook
FAA Order 6480.4	Airport Traffic Control Tower Siting Criteria
FAA Order 6480.7	Airport Traffic Control Tower and Terminal Radar Approach Control Facility Design
FAA Order 6580.2	Remote Communications Facility Siting Criteria Handbook
FAA Order 6750.16	Siting Criteria for Instrument Landing Systems
FAA Order 6820.10	VOR, VOR/DME, and VORTAC Siting Criteria
FAA ER 530-81-04	Structural/Mechanical Design Requirements for Low Impact Resistance for Microwave Landing System Structures (MLS/LIRS)
FAA E-2470	Transparent Plastic Window Shades

(Unless otherwise indicated, copies are available from the U.S. Department of Transportation, Utilization and Storage Section, M-443.2, Washington, DC 20590.)



MIL-HDBK-1024/1

National Plumbing Code Handbook, McGraw-Hill Book Company

(Unless otherwise indicated, copies are available from the McGraw-Hill Book Company, 1221 Avenue of the Americas, New York, NY 10020.)

Uniform Federal Accessibility Standards (UFAS)

(Unless otherwise indicated, copies are available from ATBCB, 5th Floor, Room 1711, 18th Street, N.W., Washington, D.C. 20036-3894.)

Industrial Ventilation: A Manual of Recommended Practice, Committee on Industrial Ventilation, P.O. Box 453, Lansing, MI 48902

(Unless otherwise indicated, copies are available from the American Conference of Governmental Industrial Hygienists, 6500 Glenway Avenue, Building D-7, Cincinnati, OH 45211-4438.)

## MIL-HDBK-1024/1

## GLOSSARY

AC. Advisory circular.

ACDS. Advanced combat direction system.

ADP. Automated data processing.

A-E. Architectural-engineer.

AFFF. Aqueous film forming foam.

ARSR. Air route surveillance radar.

ASCOMM. ASWOC support communications.

ASHRAE. American Society of Heating, Refrigerating, and Air Conditioning Engineers.

ASR. Airport surveillance radar.

ASTM. American Society for Testing and Materials.

ASUW. Anti-surface warfare.

ASW. Anti-submarine warfare.

ASWOC. Anti-submarine warfare operations center.

ATC. Air traffic control.

ATCRBS. Air traffic control radar beacon system.

BEAP. Base Exterior Architecture Plan.

BESEP. Base Electronic Systems Engineering Plan.

CCTV. Closed circuit television.

CFR. Code of Federal Regulations.

CNO. Chief of Naval Operations.

COMNISCOM. Commander, Naval Investigative Service Command.

DCS. Defense Communications System.

DIA. Defense Intelligence Agency.

MIL-HDBK-1024/1

DISA. Defense Informational Systems Agency.

DME. Distance measuring equipment.

DOD. Department of Defense.

EMR. Electromagnetic radiation.

ER. Engineering report.

ESS. Electronic sensor system.

FAA. Federal Aviation Administration.

FASFAC. Fleet area control and surveillance facilities.

GCA. Ground controlled approach.

HEMP. High altitude electromagnetic pulse.

IDS. Intrusion detection systems.

IDSEP. Intrusion detection systems engineering plan.

IFR. Instrument flight rules.

ILS. Instrument landing system.

JCF. Joint control facility.

MILCON. Military construction.

MLS. Microwave landing system.

MTRACON. Military terminal radar.

NAALS. Air navigation aids and landing systems.

NAVAIDS. Navigation aids.

NAVAIRSYSCOM. Naval Air Systems Command.

NAVFACENCOM. Naval Facilities Engineering Command.

NAVOCEANCOM. Naval Oceanography Command.

NAVOCEANO. Naval Oceanographic Office I.C.

NCCS. Navy command and control systems.

MIL-HDBK-1024/1

NESSEC. Naval Electronics Systems Security Engineering Center.

NFPA. National Fire Protection Association.

NISE-EAST. Naval-in-Service Engineering, East Coast Division, Charleston, SC.

NISE WEST. Naval Command, Control, and Ocean Surveillance Center In-Service Engineering, West Detachment, Vallejo, CA.

NTDS. Navy tactical data system.

OCIP. Operational capability improvement request.

OPNAV. Operations Navy.

OTHT. Over the horizon targeting.

PALS. Precision approach landing system.

PAR. Precision approach radar.

POV. Privately owned vehicle.

RASS. Range airspace surveillance sites.

RATCF. Radar air traffic control facility.

RF. Radio frequency.

ROC. Range operations center.

SPAWARSYSCOM. Space and Naval Warfare Systems Command.

SPINTCOM. Special Information Command.

TACAN. Tactical air navigation.

UHF. Ultra high frequency.

UL. Underwriters Laboratories, Inc.

UPS. Uninterrupted power supply.

VFR. Visual flight rules.

VHF. Very high frequency.

VOR. Very high frequency omni-directional range.

MIL-HDBK-1024/1

VORTAC. Very high frequency omni-directional range/tactical air navigation.

CUSTODIAN  
NAVY - YD2

PREPARING ACTIVITY  
NAVY - YD2

PROJECT NO.  
FACR-1086